



Republic of the Philippines
CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

REQUEST FOR QUOTATION
NO.: RFQ-2022-075

Date: October 28, 2022

Name of the Company : _____
Address : _____
Contact No. : _____
PhilGEPS Registration No. : _____

Sir/Madam:

Please quote your best offer (lowest net, price, taxes, and government discount terms included) and submit your Quotation duly signed by you or your duly authorized representative not later than November 4, 2022 at 9:00AM for:

Name of the Project : **REHABILITATION OF AIRPORT PERIMETER FENCE AT BAGUIO AIRPORT**
Location : **BAGUIO AIRPORT, BAGUIO CITY**
Terms of Reference :

Sealed quotations must be submitted either personally to Ms. Hazelle May C. Andres, Head, Secretariat of the Bids and Awards Committee of Laoag International Airport (BAC-LIA) or e-mail at areacenter1_bac@caap.gov.ph. For any clarification, do not hesitate to contact us through the contact information seen below.

Aside from the Terms and Conditions provided at the back portion of this RFQ, please observed the following general conditions:

- The following documents must be attached upon submission of the Quotation:
 - Mayor's Permit
 - PhilGEPS Certificate of Registration
- All quotations shall be considered as fixed price and not subject to price escalation during the contract implementation.
- Payment shall be made through check.

Atty. RIZZA JOY S. VALLESTERO
Chairperson, Bids and Awards Committee

After having carefully read and accepted the Terms and Conditions, I/We submit our quotations for the following item/s:

ITEM DESCRIPTION (SPECIFY THE BRAND AND MODEL OF YOUR OFFER/PROPOSAL, IF APPLICABLE)	APPROVED BUDGET OF THE CONTRACT (ABC)	OFFER*						
		PRICE				Compliance w/ Technical Specifications		REMARKS
		QTY	UNIT	Unit Price	Total Price	Yes	No	
1. Supply of labor and materials which will be used for the project titled: “REHABILITATION OF AIRPORT PERIMETER FENCE AT BAGUIO AIRPORT” Scope of Works: 1. Site Works 2. Concrete Works	₱299,027.84	1	Lot					



3. Steel Works								
4. Painting Works								
No. of Days to Complete: Thirty (30) Calendar Days								
TOTAL ABC	₱299,027.84							
GRAND TOTAL:								

Note: Quotation for each item must not exceed the ABC per item

Signature over Printed Name
Supplier/Dealer/Contractor

TERMS AND CONDITIONS

1. Bidders shall provide correct and accurate information required in this form.
2. Price quotation/s must be valid for a period of Thirty (30) calendar days from the date of submission.
3. Price quotation/s shall be denominated in Philippine Peso which includes all taxes, duties and/or levies payable.
4. Quotations exceeding the ABC shall be rejected.
5. Award of contract shall be made to the lowest quotation (for goods and infrastructure) or, the highest rated offer (for consulting services) which complies with the minimum technical specifications and other terms and conditions stated herein. Further, the most advantageous to the government to the point of quality of materials and prices as well as the responsiveness of the bids shall be the basis of the award.
6. *The Head of the Procuring Entity reserves the right to reject any and all bids, declare a failure of bidding or not award the contract in any of the following conditions set forth by Sec. 41 (Reservation Clause) of the Revised IRR of RA 9184.*
7. The Supply Office of LIA shall have the right to inspect and to test the goods to confirm their conformity to the technical specifications.
8. *Date of Completion/Delivery:* In case of an approved POW, within the period stated therein. While, in cases of regular procurement, within 7-10 days or less, after the issuance of the Purchase Order. Further, any request of extension shall be sent to the End-User/Implementing Facility concern.
9. *Mode and Terms of Payment:* Within ten (10) working days after the supplies/materials and labor/service have been inspected and accepted, respectively, through a check issued by the procuring entity.
10. Liquidated damages equivalent to one tenth of one percent (0.001%) of the value of the goods not delivered within the prescribed delivery period shall be imposed per day of delay. This Office (LIA) shall rescind the contract once the cumulative amount of liquidated damages reaches ten percent (10%) of the amount of the contract, without prejudice to other courses of action and remedies open to it.

NOTE: The aforecited Terms and Conditions shall be without prejudice to any provisions of a Contract which will be executed by and between the Procuring Entity and Contractor/Supplier/Dealer in order to conform with the requirements set forth by RA 9184.

NAME OF PROJECT : REHABILITATION OF AIRPORT PERIMETER FENCE
LOCATION : BAGUIO AIRPORT, BAGUIO CITY, BENGUET
SUBJECT : BILL OF MATERIALS AND COST ESTIMATES

A. REHABILITATION OF AIRPORT PERIMETER FENCE 52.00 l.m.

SITE WORKS

A. Activities included:			
	Excavation	13.00	cu.m.
B. Labor			
Qty.	Days	Rate/Day	Amount
	Foreman		
	Common Workers		

CONCRETE WORKS 2.32 cu.m

A. Materials			
Qty.	Units	Description of Materials	Unit Cost
	pcs.	6" CHB	
	bags	Portland Cement, 40kgs	
	cu.m.	Sand	
	cu.m.	3/4 Gravel	
	pcs.	12mmØ RSB, 6m	
	pcs.	10mmØ RSB, 6m	
	roll	#16 G.I. Tie Wire	
	pcs.	Cutting Disk, 14"	
B. Labor			
Qty.	Days	Rate/Day	Amount
	Foreman		
	Skilled Workers		
	Common Workers		
C. Equipment			
Qty.	Days	Rate/Day	Amount
	One-Bagger Mixer		
	Cut-off Machine		
	Generator Set		

STEEL WORKS 1.00 lot

A. Materials			
Qty.	Units	Description of Materials	Unit Cost
	pcs.	50mmØ x 20' G.I. Pipe, S-40	
	rolls	Barbed Wire, 140 m.	
	boxes	Welding Rod	
B. Labor			
Qty.	Days	Rate/Day	Amount
	Foreman		
	Skilled Workers		
	Common Workers		
C. Equipment			
Qty.	Days	Rate/Day	Amount
	Portable Welding Machine		

Handwritten signature or mark.

NAME OF PROJECT : REHABILITATION OF AIRPORT PERIMETER FENCE
LOCATION : BAGUIO AIRPORT, BAGUIO CITY, BENGUET
SUBJECT : BILL OF MATERIALS AND COST ESTIMATES

PAINTING WORKS				1.00	lot
A.	Materials				
	Qty.	Units	Description of Materials	Unit Cost	Amount
		gals.	Quick Dry Enamel Paint		
		gals.	Epoxy Primer		
		pcs.	3" Paint Brush		
		L	Paint Thinner		
B.	Labor				
	Qty.	Days		Rate/Day	Amount
			Foreman		
			Common Workers		
Total Material Cost					
Total Labor Cost					
Total Equipment Rental Cost					
Total Direct Cost					



Republic of the Philippines
CIVIL AVIATION AUTHORITY OF THE PHILIPPINES
Old Mia Road corner Ninoy Aquino Avenue
1300 Pasay City, Metro Manila

Name of the Project : Rehabilitation of Airport Perimeter Fence at Baguio Airport
Location : Loakan, Baguio City, Benguet
Duration : Thirty (30) Calendar Days

SCOPE OF WORK

The project covers the supply of labor, materials, tools/equipment necessary for the **Rehabilitation of Airport Perimeter Fence at Baguio Airport**. The details of work are best enumerated below, however, it is understood that the contract includes all works and services although not specifically mentioned herein, but are needed to fully complete the project.

The following scopes of work shall be done in accordance with the approved plans, specifications and provision of contract.

I. CIVIL/STRUCTURAL WORKS

a) Site works

The work includes the supply of labor and tools needed for site works including excavation for structural footings as indicated on the plan.

b) Concrete Works

The work includes the supply of labor, materials, tools and equipment needed to complete the concreting components of the structure such as column footings, columns, wall footings/footing tie beams, installation and stripping of formworks, fabrication and installation of reinforcing steel bars as indicated on the plans.

c) Steel Works

The work includes the supply of labor, materials, tools and equipment needed to complete the steel works including fabrication and installation of G.I. pipes, and barbed wires as indicated on the plan.

II. ARCHITECTURAL WORKS

d) Painting Works

The work includes materials, labor, and tools needed to complete the painting works for G.I. pipe as indicated on the plan.

All scopes of work to this item must be according to plans and specifications and approved by the Project In-Charge. Also, quality and types of materials must conform and must be approved by the Project Engineer assigned by CAAP.

The contractor shall be responsible in providing safety perimeter fence or security fences, personal protective equipment (PPE) for staffs and workers, and Safety Inspectors or Safety Engineers on site while construction is ongoing. Regular safety reports should be accomplished.

The contractor shall be responsible for all laboratory, material testing, environmental compliance certificate (ECC), building and safety permits and survey instruments necessary in the project implementation. All expenses shall be incorporated in the contractor's overhead cost and shall not be considered as pay item.



DEPARTMENT OF TRANSPORTATION AND COMMUNICATIONS
CIVIL AVIATION AUTHORITY OF THE PHILIPPINES
1000, 1000, 1000

THIS DRAWING IS THE EXCLUSIVE PROPERTY OF CIVIL AVIATION AUTHORITY OF THE PHILIPPINES AND MUST NOT BE REPRODUCED, EXHIBITED, LOANED OR COPIED IN PART OR IN WHOLE WITHOUT PROPER PERMISSION AND/OR WRITTEN CONSENT FROM THE DIRECTOR GENERAL CAAP.

AERODROME DEVELOPMENT AND MANAGEMENT SERVICE

INFRASTRUCTURE DEVELOPMENT AND DESIGN DIVISION

DESIGN STAFF	INITIAL / DATE
DESIGNED BY: JDD	
DRAWN BY: JRP	
REVIEWED BY: F.S.	
DATE:	

CHECKED BY:
ENGR. J. LAMARCA
Aeronautical Engineer III, RMD-ADMS
CAAP

SUBMITTED BY:
RENNE A. SANTIAGO
Division Chief III, RMD-ADMS
CAAP

RECOMMEND APPROVAL:

ARNEL F. BORLADO
Department Manager III, ASD-ADMS

APPROVED:
LT COL VALENTIN A. DIONELA PAF (RET)
Assistant General III - ADMS


NOTES/REVISIONS:

PROJECT: REHABILITATION OF AIRPORT PERIMETER FENCE


LOCATION: BAGUIO AIRPORT
LOAKAN, BAGUIO CITY, BEGUET

SHEET CONTENTS: AS SHOWN

DRAWING SCALE:	SHEET NO:
AS SHOWN	AS
	1




S-6
AS-1/AS-1
DETAIL OF BARBED WIRE
FIXER WELDED TO G.I. PIPE




S-5
AS-1/AS-1
DETAIL OF G.I. PIPE
EMBEDDED ON CONCRETE POST


- NOTE:
- CHB WALL SHALL BE COSTURA FINISH (BOTH FACE).
 - CONCRETE COLUMNS SHALL BE CEMENT PLASTERED FINISH.
 - G.I. PIPE SHALL BE SCHEDULE 40.
 - PAINTINGS ALL G.I. PIPES SHALL BE PAINTED WITH RED LEAD OXIDE, RED LEAD, OR EPOXY PRIMER AS SPECIFIED BEFORE FINAL COAT IS APPLIED.




A-2
AS-1/AS-1
FRONT ELEVATION
SCALE 1:30 H15




A-1
AS-1/AS-1
PLAN OF FENCE
SCALE 1:30 H15




S-1
AS-1/AS-1
FOUNDATION PLAN
SCALE 1:30 H15




A-3
AS-1/AS-1
SECTION THRU "A"
SCALE 1:20 H15



S-4
AS-1/AS-1
WALL FOOTING DETAIL
SCALE 1:20 H15




SECTION




PLAN

S-2
AS-1/AS-1
DETAIL OF C1F1
SCALE 1:20 H15



SECTION



PLAN

S-3
AS-1/AS-1
DETAIL OF C2F2
SCALE 1:20 H15