Republic of the Philippines CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

23 September 2022 Date

REQUEST FOR QUOTATION

Sir/Madam:

Please quote your lowest net prices, taxes, including Government discount terms, and period of delivery of the following items listed hereunder for the account of the official use of the Civil Aviation Authority of the Philippines (CAAP), Area Center V, Bicol International Airport in connection with the implementation of the Repair & Maintenance Of Windcone Stand Including Concrete Base Slab At Virac Airport project. It is requested that price quotations be submitted in an envelope, duly sealed, to be opened by our Bids and Awards Committee on <u>04 October 2022</u> at <u>2:00 pm</u> at the BAC Office, Ground Floor, Admin Bldg, Bicol International Airport (BIA), Daraga, Albay.

The following should be submitted together with the quotation:

- 1. Valid PCAB License Small A;
- 2. Current Mayor's/Business Permit;
- 3. Phil-GEPS Registration Number; and
- 4. Name/credentials of proposed Construction Foreman, and Safety Officer.
- 5. List of Contractor's Equipment (One Bagger Cement Mixer, Bar Cutter, Oxy-acetylene Cutting Torch and Portable Welding Machine)
 (The contractor's major equipment units, which are owned, leased, and/or under purchase agreements must be supported by proof of ownership, certification of availability of equipment from the equipment lessor/vendor for the duration of the project, as the case may be, which must meet the minimum requirements)
- 6. Other documentary requirements:
- 6.1 Omnibus Sworn Statement (see attached format, maybe submitted together with the quotation or before issuance of Notice of Award.)
- 6.2 Additional Requirements to be submitted before issuance of Notice To Proceed:
 - 6.2.1 Work Schedule;
 - 6.2.2 PERT/CPM;
 - 6.2.3 S-Curve;
 - 6.2.4 Manpower Schedule;
 - 6.2.5 Work Method;
 - 6.2.6 Construction Safety & Health Programs Approved by the DOLE*; and
 - 6.2.7 Performance Security.

^{*}Copy of the CSHP received by the DOLE may be initially submitted together with the NOA, however, the DOLE approved CSHP must be immediately submitted upon approval.

Quotations not accompanied by valid PCAB License; current Mayor's/Business Permit; Phil-GEPS Registration Number; name/credentials of proposed Construction Foreman, and Safety Officer; and list of contractor's equipment together with supporting documents shall be automatically disqualified.

SCOPE OF WORK:

- 1.) Provision of project billboard & PPE's
- 2.) Site Works: Excavation for the new location of 1-unit windcone assembly.

Removal of existing dilapidated windcone assembly.

3.) Civil Works: Concreting works for the windcone pedestal & assembly base according to

plans.

- 4.) Steel Works: Fabrication & installation of 1-unit windcone assembly according to plans.
- Painting Works: 1-coat Primer and 2-coats Finish concrete base (Latex Paint).
 1-coat Primer and 2-coats Finish windcone pedestal (QDE).
- 6.) Upkeep of project site at all times & provision of construction barriers/signages.
- 7.) Incidentals are to be provided by the contractors as part of the OCM pay item.
- 8.) Provision of minor tools and equipment necessary for the execution of work.

PLEASE ACCOMPLISH THE FOLLOWING ATTACHED FORMS:

- 1. Bid Proposal (Annex "A")
- 2. Bill Of Quantities (Annex "B")
- 3. Detailed Estimate Form (Annex "C")

NOTE:

All pages of the Annexes must be duly signed by the bidder or his authorized representative. Bids/quotations not addressing or providing all of the required items where applicable shall be considered non-responsive and thus, automatically disqualified. In this regard, where a required item is provided, but no price is indicated, the same shall be considered non-responsive, but specifying a zero (0) or a dash (-) for the said item would mean that it is being offered for free.

(Contractor's Logo On Main Page)

BID PROPOSAL

Repair & Maintenance Of Windcone Stand Including Concrete Base Slab At Virac Airport

ITEM	DESCRIPTION OF WORK	QUANTIT	N F	QUANTIT UNI ESTIMATED PERCENT	MARK- PERC	IARK-UPS IN PERCENT		TOTAL MARK-UP	VAT	TOTAL	TOTAL NOTAL COST INIT COST	TAUTTOOST
		-	-	I DIRECTOST	0CM	OCM Profit	%	VALUE		COST		100011100
(1)	(2)	(3)	(4)	(5)	(9)	0	(%)	(9) (5) x (8)	$(10) \qquad (11) \qquad (11) \qquad (28) \times (25) + (9) \qquad (29) + (10)$	(11)	(12)	(13)
SPL	SITE WORKS	1.00	pt							61 6	(11)	(0)(71)
1.00	CIVIL WORKS											
1.01	1.01 CONCRETE WORKS	1.00	lot									
2.00	ARCHITECTURAL WORKS											
2.01	STEEL WORKS	1.00	lot									
2.02	2.02 PAINTING WORKS	1.00	lot									
	TOTAL AMOUNT									Arthur .		

Submitted by:	
Printed Name:	
Position:	
Name Company:	
Date:	

(Contractor's Logo On Main Page)

BILL OF QUANTITIES

Project: Repair & Maintenance Of Windcone Stand Including Concrete Base Slab At Virac Airport

Item No	Description	Qty	Unit	Unit Price	Amount
SPL	SITE WORKS				
	Pesos Amount in Words	1.00	lot		
	and centavos	100	5		
1.00	CIVIL WORKS				
1.01	Concrete Works				
	Pesos Amount in Words	1.00	lot		
	and centavos				
2.00	ARCHITECTURAL WORKS				
2.01	Steel Works				
	Pesos Amount in Words	1.00	lot		
	and centavos				
2.02	Painting Works				
	Pesos Amount in Words	1.00	lot		
	and centavos				

Total Bid Amount (Php):			
Total Bid Amount in Words:			
		-	
	Submitted by:		
	Printed Name:		
	Position:		
	Name Company:		
	Date:		

LOC	ATION : Repair & Maintenance Of Windstrand : Virac Airport : Virac Airport, Virac, Catandu : Bill of Quantities		d Including Conc	rete Base Slab	Annex
TEM	DESCRIPTION	OUANTIT	y UNIT	UNIT PRICE	AMOUNT
SPL	SITE WORKS				711100111
	Labor Cost				
	Excavation for New Location of Windcone Assembly	1.00	lot		
	Removal of Existing Windcone Assembly	1.00	kot		
	(Proper turnover of waste materials)	1.00			
			Labor Cost	***************************************	
	CIVIL WORKS			7.00	
0.00	CONCRETE WORKS				
A	MATERIAL COST				
	Windcone pedestal:				
	Cement	11.00	bag		
	Sand	1.00	m³		
	3/4" Gravel	2.00	m³		
	RSB 16m Ø, 6m	6,00	рс		
	GI Tie Wire, #16	1.00	kg	The state of	
	Forms & Scaffoldings:	TANKES.	1		
	Ordinary Plywood 1/4" Thk.	2.00	pc		
	Coco Lumber 2"x2"	6.00	bdft		
	Common Nails Assorted	1.00	kg		
		1.00			
	16 00-3 C P	423	Material Cost		
	16.90m³ Concrete Base (1-unit 15mX15mX75mm thk):				
- 3	Cement	108.00	bag		
	Sand	9.00	m³		
- 4	3/4" Gravel	18.00	m³		
347	RSB 10mmø, 6m	150.00	pc		
	GI Tie Wire, #16	6.50	kg		
	Forms & Scaffoldings:				
	Ordinary Plywood 1/4" Thk.	3.00	pc		
	Coco Lumber 2"x2"	17.00	bdft		
	Common Nails Assorted	1.00	kg		
			Material Cost.		
В	LABOR COST	QTY	DUR. (DAYS)	RATE/DAY	10.010.000.000.000
	Foreman	1	12	TOTALDITT	
	Skilled Labor	2	12		
	Common Labor	2	12		
		2			
	EQUIPMENT NEW YORK AND ADDRESS OF THE PARTY		Labor Cost		
C	EQUIPMENT RENTAL COST	QTY	DUR. (DAYS)	RATE/DAY	
	One Bagger Cement Mixer	1	1		
- 4	Bar Cutter	1	5		
			Equipment Cost		
A	TOTAL MATERIAL COST				
В	TOTAL LABOR COST				
C	TOTAL EQUIPMENT COST				
D	TOTAL DIRECT COST				
	INDIRECT	COSTS	3		
1. 00			ed Direct Cost		
2. CO	NTRACTOR'S PROFIT 10.0%		ed Direct Cost		
	TAL OCM & PROFIT 18.0%	of D			
	LUE ADDED TAX, (VAT) 5.0%	of (D + E)		1	
	TAL ESTIMATED INDIRECT COST (F+E), P	(5 , 15)			
. TO	TAL ESTIMATED UNIT INDIRECT COST (G/Quantity), P/Unit			

Submitted by:	
Printed Name:	
Position:	
Name Company:	
Date:	

							Annex
NAN	ME OF PROJECT	1	Repair & Maintenance Of	f Windcone Stand	Including Concr	ete Base Slab	
			At Virac Airport				
LOC	CATION	1	Virac Airport, Virac, Cata	nduanes			
SUB	JECT	1	Bill of Quantities				
TEN	1	DES	CRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
2.00	ARCHITECTURAL	WOR	KS	233373332	Ortif	OMITIMEL	AMOONT
2.01	STEEL WORKS						
A	MATERIAL COST						
	Windcone pedestal:						
	3/4" X 800mmL	Ancho	or Bolt w/ washers	6.00	рс		
	1/2" X 2" Bolt w	/ nut &	washers	10.00	рс		
	1/4" X 5" Bolt w	/ nut &	washers	1.00	рс		
	3/8" X 5" Stainle	ss Bol	t w/ nut & washers	2.00	рс		
	80mm X 80mm	X 6mn	thk Tubular Pipe, 6m	1.00	рс		
	1 1/2" GI pipe, 6			0.50	рс	7777	
	10mmФ Plain ro	und Ba	ar, 6m	1.00	рс	الرستار مردد مالات	
	1 1/2" Sealed Be			2.00	pc		
	10mm thk MS P	late		1.00	рс		
	Welding Rod			10.00	kg		
	Nylon Cord, me	dium		30.00	lnm		
					Material Cost		
В	LABOR COST			QTY	DUR (DAYS)	RATE/DAY	
	Foreman			1	3	KATE/DAT	
	Skilled Labor			2	3		
	Common Labor			2	3		
0	EQUIDA (ENTE NO ENTE		L .		Labor Cost		
С	EQUIPMENT RENT			QTY	DUR. (DAYS)	RATE/DAY	
	Portable Welding			1	3		
	Oxy-acetylene c	utting 1	orch	1	3		
	Bar Cutter			1	3		
					Equipment Cost		
A	TOTAL MATERIAL	72	Γ				
В	TOTAL LABOR CO						
C	TOTAL EQUIPMEN		ST				
D	TOTAL DIRECT CO	ST					
			INDIRE				
	CM	1	8.0%		d Direct Cost		
	ONTRACTOR'S PROF	100	10.0%		d Direct Cost		
	OTAL OCM & PROFI	200	18.0%	of D			
	LUE ADDED TAX, (5.0%	of (D + E)			
			ECT COST (F+E), P				
			NDIRECT COST (G/Qua	ntity), P/Unit			
	AL ESTIMATED COS	_					
OT	AL ESTIMATED UNI	I CO	ST (Total Estimated Cost / C	Quantity), P/Unit			
			Subr	nitted by:			1.7
				ted Name:			
			Posi				
				ne Company:			