



Republic of the Philippines
CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

REQUEST FOR QUOTATION

Date: _____
P.R./APP No.: 10604010-0984

Company Name: _____
Address: _____

Please quote your lowest price on the items / listed below, subject to the General Condition on the last page, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than _____ in the return envelope attached herewith

Very truly yours,


ROLDAN P. ABEJUELA
BAC Chairman

- Note 1. All entries must be legibly hand-written/computerized.
2. Delivery Period within ___ calendar days.
3. Warranty shall be for a period of six (6) months for supplies and materials, one (1) year for Equipment, from date of acceptance by the procuring entity.
4. Price validity shall be a period of 30 calendar days.
5. G-EPIS Registration Certificate shall be attached upon submission of the Quotation.
6. Bidders shall submit Original Brochures showing certification of the product being offered (optional).
7. Mode of delivery shall be assigned by the Procuring Entity.
8. Bids not using the official form (with BAC Logo) shall be automatically disqualified.

ITEM NO.	UNIT	COMPLETE DESCRIPTION OF ARTICLES	QTY.	UNIT PRICE	AMOUNT
Construction of CSIS Office					
Piaridel Airport					
1.00 CIVIL/STRUCTURAL WORKS					
1.01 Removal Works					
A. Materials					
1	cu.m.	Gravel, G1	2.00		
2	cu.m.	Common Borrow (Embankment, delivered on site)	9.00		
3	gals	Soil Poisoning	13.00		
4	pcs	Diamond Blade Cutter 14" Ø	1.00		
B. Labor					
	DUR. (DAYS)				
5	7	Project (Civil) Engineer	1.00		
6	7	Construction Foreman	1.00		
7	7	Skilled Worker	2.00		
8	7	Common Worker	4.00		
C. Equipment					
	DUR. (DAYS)				
9	5	Air Compressor and Jackhammer	1.00		
10	1	Concrete Saw, Blade 14" diameter	1.00		
11	1	Plate Compactor	1.00		
1.02 Concrete Works					
A. Materials					
12	bags	Portland Cement	163.00		



13	cu.m.	Sand	9.00		
14	cu.m.	Gravel, 3/4"	17.00		
15	pcs	16mm dia. DRSB, 6meters	115.00		
16	pcs	12mm dia. DRSB, 6meters	19.00		
17	pcs	10mm dia. DRSB, 6meters	165.00		
18	kgs	#16 GI Tie Wire	29.00		
19	pcs	1/2" x 4' x 8' Ordinary Plywood	17.00		
20	bd.ft	Form Lumber	1014.00		
21	kgs	Assorted CWN	19.00		
	DUR. (DAYS)	B. Labor			
22	10	Project (Civil) Engineer	1.00		
23	18	Construction Foreman	1.00		
24	18	Skilled Worker	2.00		
25	18	Common Worker	4.00		
	DUR. (DAYS)	C. Equipment			
26	3	One-bagger Concrete Mixer	1.00		
27	3	Concrete Vibrator	1.00		
		1.03 Masonry Works			
		A. Materials			
28	pcs.	150mm thick CHB	1188.00		
29	bags	Portland Cement (40kg)	124.00		
30	cu.m.	Sand	11.00		
31	pcs.	10mm dia. DRSB, 6meters	67.00		
32	kgs.	#16 GI Tie Wire	4.00		
	DUR. (DAYS)	B. Labor			
33	3	Project (Civil) Engineer	1.00		
34	6	Construction Foreman	1.00		
35	6	Skilled Worker	2.00		
36	6	Common Worker	4.00		
		1.04 Steel Works			
		A. Materials			
		(Roof Frame, including Guard Post roof frame)			
37	pcs.	3" Ø x 6m G.I. Steel Pipe, Sch. 40	1.00		
38	pcs.	1 1/2" x 10mmØ Anchor bolt with washers	68.00		
39	pcs.	1 1/2" x 12mmØ Anchor bolt with washers	84.00		
40	pcs.	50mm x 50mm x 4.76mm x 6m. Angle bar	19.00		
41	pcs.	44mm x 44mm x 4.76mm x 6m. Angle bar	11.00		
42	pcs.	32mm x 32mm x 4.76mm x 6m. Angle bar	4.00		
43	pcs.	25mm x 25mm x 4.76mm x 6m. Angle bar	3.00		
44	pcs.	100mm x 50mm x 1.5mm x 6m. C-purlins	24.00		



45	pcs.	50mm x 50mm x 1.5mm x 6m. C-purlins	3.00		
46	pcs.	6mm thk. Gusset Plate (1.2m x 2.4m)	2.00		
47	pc.	10mm thk. Base Plate (1.2m x 2.4m)	1.00		
48	kgs	Welding rod E6011	10.00		
49	cyl	Oxygen	3.00		
50	cyl	Acetylene	3.00		
	DUR. (DAYS)	B. Labor			
51	g	Construction Foreman	1.00		
52	g	Skilled Worker	1.00		
53	g	Common Worker	2.00		
	DUR. (DAYS)	C. Equipment			
54	g	Welding Machine	1.00		
55	g	Portable Generator Set	1.00		
56	g	Oxy-Acetylene Cutting Torch/Welding Outfit	1.00		
		1.05 Roofing Works			
		A. Materials			
57	ln.m.	GA #24 Longspan Rib-type Pre-painted Roofing Sheet	138.00		
58	pcs.	G.I Gutter GA #24, Pre-painted	18.00		
59	pcs.	G.I Valley Roll GA #24 (0.50mm thk x 0.610m x 2.44m), Pre-painted	2.00		
60	pcs.	G.I Flushing GA #24 (0.50mm thk x 0.915m x 2.44m), Pre-painted	2.00		
61	pcs.	G.I Ridge Cap GA #26 (0.40mm thk x 0.610m x 2.44m), Pre-painted	14.00		
62	pcs.	Polyethylene foam w/ one side aluminum (10mm x 1m x50m)	2.00		
63	tubes	Roof Sealant	10.00		
64	pcs.	Teksrew	1350.00		
65	pcs.	Blind Rivet 1/8" dia.	1350.00		
	DUR. (DAYS)	B. Labor			
66	g	Construction Foreman	1.00		
67	g	Skilled Worker	2.00		
68	g	Common Worker	4.00		
		1.06 Catch Basin			
		A. Materials			
69	pcs.	100mm thick CHB	24.00		
70	bags	Portland Cement	6.00		
71	cu.m.	Sand	3.00		
72	cu.m.	Gravel, 3/4"	1.00		
73	pcs.	10mm dia. DRSB, 6meters	16.00		
74	sets	12mm dia. Lifting Handle with 16mm Bolts	5.00		
75	kgs.	G.I. Tie Wires	1.00		



76	pcs.	1/2" x 4' x 8' Ordinary Plywood	1.00		
77	bd.ft.	Form Lumber	23.00		
78	kg.	Assorted CWN	1.00		
	DUR. (DAYS)	B. Labor			
79	2	Construction Foreman	1.00		
80	2	Skilled Worker	1.00		
81	2	Common Worker	2.00		
		2.00 ARCHITECTURAL WORKS			
		2.01 Tile Works			
		A. Materials			
82	pcs.	600mm x 600mm Homogenous Floor Tiles Polished Finish	116.00		
83	pcs.	300mm x 300mm Homogenous Floor Tiles	36.00		
84	pcs.	300mm x 300mm Homogenous Wall Tiles	87.00		
85	pcs.	600mm x 600mm Homogenous Polished Tiles (kitchen countertop)	2.00		
86	pcs.	Tile Trim, 8ft.	7.00		
87	bags	Tile Adhesive (25kgs)	15.00		
88	bags	Tile Grout (2kgs)	11.00		
89	pcs.	Diamond Cutting Disk, 4"	2.00		
	DUR. (DAYS)	B. Labor			
90	2	Project (Civil) Engineer	1.00		
91	4	Construction Foreman	1.00		
92	4	Skilled Worker	2.00		
93	4	Common Worker	4.00		
	DUR. (DAYS)	C. Equipment			
94	4	Angle Grinder	1.00		
		2.02 Carpentry			
		A. Materials			
		2.02.01 Dry Wall, Ceiling and Fascia Board			
		Dry Wall			
95	pcs.	4' x 8' x 6mm thk. Fiber Cement Board	9.00		
96	pcs.	32mmx64mmx3mx0.6mm thk. Metal Stud	9.00		
97	pcs.	32mmx64mmx3mx0.6mm thk. Metal Tracks	5.00		
98	pcs.	Needle Point Screw 38mm w/ plastic insert	17.00		
99	pcs.	Self Drilling Point Screw 10mm	57.00		
		Ceiling and Fascia Board			
100	pcs.	4' x 8' x 4.5mm thk. Fiber Cement Board	31.00		
101	pcs.	Wall Angle (0.6mm thk x 25mm x 25mm x 3m)	40.00		
102	pcs.	Double Furring (0.6mm thk x 19mmx50mmx5m)	40.00		
103	pcs.	Carrying Channel (12mm x 38mm x 5m)	19.00		



104	pcs.	W-Clip	257.00		
105	pcs.	Flat Head Screw 20mm	2370.00		
106	pcs.	Metal Screw 32mm with plastic insert	295.00		
107	boxes	Blind Rivets	3.00		
108	pcs.	Rod Suspension Hanger with Adjustment Spring	81.00		
109	rolls	Fiber Cement Board Perforated Tape (250ft/roll)	3.00		
110	pcs.	Fiber Cement Board Putty (25kg per pc.)	4.00		
111	pcs.	1' x 4' Air Ventilation L-Type	4.00		
112	meters	Insect Screen	4.00		
113	pcs.	Fascia Board 12mm x 12" x 12ft.	10.00		
114	pcs.	Drill Bit	10.00		
115	pcs.	Cutting Disc 4"	5.00		
116	kgs	Assorted Concrete Nails	2.00		
	DUR. (DAYS)	B. Labor			
117	12	Project (Civil) Engineer	1.00		
118	12	Construction Foreman	1.00		
119	12	Skilled Worker	2.00		
120	12	Common Worker	2.00		
	DUR. (DAYS)	C. Equipment			
121	12	Scaffolding Set	4.00		
122	12	Electric Hand Drill	2.00		
		2.03 Painting Works			
		A. Materials			
		2.03.01 Paint Finish for Exterior Wall, Interior Wall, Ceiling and Fascia Board			
123	gals	Flat Latex White Paint	14.00		
124	gals	Semi Gloss Latex Paint	25.00		
125	bags	Skimcoat (20kg)	24.00		
126	pcs.	Acry Color (1/4 liter)	5.00		
127	gals	Paint thinner	1.00		
128	pcs.	Paint Roller with pan 7"	10.00		
129	pcs.	Paint Brush 4"	10.00		
130	pcs.	Paint Brush 2"	10.00		
131	pcs.	Assorted Sand Paper	200.00		
132	kgs	Rugs	5.00		
		2.03.02 Paint Finish for Doors and other steel finishes			
133	gals	Flatwall Enamel Paint	2.00		
134	gals	Quick Dry Enamel Paint	7.00		
135	gals	Glazing Putty	2.00		
136	gals	Red Oxide Primer	4.00		
137	gals	Paint thinner	2.00		
138	pcs.	Baby Roller with handle	4.00		



139	pcs.	Paint Brush 4"	4.00		
140	pcs.	Paint Brush 2"	4.00		
141	pcs.	Assorted Sand Paper	30.00		
142	kgs	Rugs	1.00		
	DUR. (DAYS)	B. Labor			
143	3	Construction Foreman	1.00		
144	7	Skilled Worker	2.00		
145	7	Common Worker	4.00		
		2.04 Doors and Windows			
		A. Materials			
146	sets	D-1, 900mm x 2100mm Wood Type Panel door w/ jamb, Painted finish (with complete door hardware and accessories)	2.00		
147	sets	D-2, 700mm x 2100mm Wood Type Flush door w/ jamb, Painted finish (with complete door hardware and accessories)	2.00		
148	sets	W-1, 1500mm x 1200mm 1/4"thk Clear glass sliding window on analog window frame with screen (with complete window hardware and accessories)	4.00		
149	set	W-2, 800mm x 800mm 1/4"thk Clear Glass Awning Window on Analog window frame (with complete window hardware and accessories)	1.00		
	DUR. (DAYS)	B. Labor			
150	2	Project (Civil) Engineer	1.00		
151	5	Construction Foreman	1.00		
152	5	Skilled Worker	2.00		
153	5	Common Worker	2.00		
		3.00 ELECTRICAL WORKS			
		A. Materials			
		3.01 Conduits			
154	pcs	1/2" x 3m Electrical PVC Pipe	20.00		
155	pcs	3/4" x 3m Electrical PVC Pipe	20.00		
156	pcs	1" x 3m PVC Pipe	5.00		
		3.02 Conduits Fittings			
157	pcs	1/2" PVC Male Adapter with Locknut	30.00		
158	pcs	3/4" PVC Male Adapter with Locknut	30.00		
159	pcs	1" Service Entrance Cap	1.00		
		3.03 Wires and Cables			
160	box	2.0mm ² THWN/THHN Copper Wire (black)	2.00		
161	box	3.5mm ² THWN/THHN Copper Wire (black)	1.00		
162	meters	14mm ² THWN/THHN Copper Wire (black)	60.00		
		3.04 Electrical Wiring Devices			
163	sets	Duplex Convenience Outlet with plate and bracket - 15A, 250V, Universal type w/ ground	9.00		
164	sets	1 Gang Aircon Outlet Set	2.00		
165	sets	2-gang switch with plate and bracket	2.00		
166	set	3-gang switch with plate and bracket	1.00		
167	set	Ground Fault Circuit Interrupter Outlet (GFCI)	1.00		




		3.05 Lighting Fixtures			
168	pcs	LED Panel Light surface mount 24W 120cm x 30cm	6.00		
169	pcs	LED Panel Light surface mount 24W 60cm x 60cm	1.00		
170	pcs	Outdoor LED Pinlight 12W	5.00		
		3.06 Ventilation			
171	pcs	30 Watts Ceiling Mounted Exhaust Fan	1.00		
		3.07 Boxes and Pullboxes			
172	pcs	PVC Octagonal Junction Box	12.00		
173	pcs	4" x 2" PVC Utility Box for 1/2" PVC Pipe	5.00		
174	pcs	4" x 2" PVC Utility Box for 3/4" PVC Pipe	15.00		
175	pcs	PVC Pull Box 4" x 6" x 6"	2.00		
		3.08 LPP / Circuit Breaker			
176	assy	6 Branch Lighting and Power Panel Board	1.00		
		1 dia, 2W, 240/120V, 60Hz, with Ground			
		Main: 100AT, 100AF, 2-Pole, 240V, 10KAIC MCCB			
		Branches: 2x30AT, 2-Pole, 10KAIC, 230V			
		Bolt on Type			
		2x20AT, 2-Pole, 10 KAIC, 230V, Bolt on Type			
		Enclosure: NEMA-1			
		Materials: G.I. #16			
		Finished: Powder Coated Gray Finish			
		Panel Features: Pushlock, Grounding Lugs, Neutral Lugs, Bolted Dead Front, Directory Holder			
		3.09 Termination Accessories			
177	pcs	Electrical Tape, 19mm x 0.19mm x 16m	5.00		
178	kg	G.I. Tie Wire GA 16	2.00		
179	pc	Rubber Tape	1.00		
180	pc	PVC Cement (100cc)	2.00		
		3.10 Hangers and Supports			
181	pcs	Conduit hanger clamp for 1/2"	50.00		
182	pcs	Conduit hanger clamp for 3/4"	50.00		
183	pcs	Conduit hanger clamp for 1"	10.00		
	DUR. (DAYS)	B. Labor			
184	15	Electrician	2.00		
		4.00 MECHANICAL WORKS			
		A. Materials			
		4.01 Air Conditioning Unit			
185	set	1.0 HP, Dual Inverter Compressor, 70% Energy Saving, Fast Cooling, Low Noise, Auto Clean, Active Energy Control Split Type ACU w/ complete standard accessories (Circuit breaker protection in NEMA 3R Enclosure, Copper tubing, pipes, rubber insulations, ACCU metal bracket platform, hangers & supports, wall mounted slimduct line set ducting system and other standard fittings), Power Supply: 230V 1Ø, 60 Hz, Refrigerant Type: R32, included labor installation.	1.00		



Official
Copy

186	set	2.0 HP, Dual Inverter Compressor, 70% Energy Saving, Fast Cooling, Low Noise, Auto Clean, Active Energy Control, Split Type Air Conditioning Unit with complete standard accessories (Circuit breaker protection in NEMA 3R Enclosure, Copper tubing, rubber insulations, ACCU metal bracket platform, hangers & supports, wall mounted slimduct line set ducting system and other standard fittings), Power Supply: 230V 1Ø, 60 Hz, Refrigerant Type: R32, included labor installation.	1.00		
5.00 PLUMBING WORKS					
A. Materials					
5.01 Fixtures					
187	set	Water Closet; American White color, elongated bowl, Vitreous China; Grade A, dual flush push button flush type mechanism, with complete fittings	1.00		
188	set	Bidet spray w/ complete accessories, Chrome plated ABS body	1.00		
189	set	Lavatory; American White color, countertop installation type, Vitreous China; Grade A, with complete accessories and fittings	1.00		
190	set	Urinal; American White color, Wall hung installation type, Top Inlet type, including Flush valve fitting for urinal, Vitreous China; Grade A, with complete accessories and fittings	1.00		
191	pcs	Wash Basin Faucet; Brass with Chrome Finish, Quarter turn lever lavatory sink faucet, with complete fittings and accessories	1.00		
192	pcs	Soap Holder; Wall mounted, American White color, Vitreous China; Grade A	1.00		
193	pcs	Toilet Paper Holder; Wall mounted, American White color, Vitreous China; Grade A	1.00		
194	pcs	Floor drain, 100mm x 100mm, stainless steel	1.00		
5.02 Sewer Line					
195	pcs	4"Ø PVC Pipe (Series 600), 3meters	2.00		
196	pcs	4"Ø x 2"Ø PVC Wye Reducer	3.00		
197	pcs	4"Ø PVC Wye	3.00		
198	pcs	4"Ø PVC Tee	3.00		
199	pcs	2"Ø PVC Pipe (Series 600), 3meters	3.00		
200	pcs	2"Ø PVC P-trap	4.00		
201	pcs	2"Ø x 2"Ø PVC 90deg. Elbow	5.00		
202	pc	2"Ø x 2"Ø PVC Coupling	3.00		
203	pcs	2"Ø PVC Wye	3.00		
204	pcs	2"Ø PVC Tee	3.00		
205	can	Solvent Cement (400cc)	1.00		
5.03 Water Line					
206	pcs	1/2"Ø PVC Pipe	3.00		
207	pcs	1/2"Ø PVC 90deg. Elbow	5.00		
208	pcs	1/2"Ø PVC 90deg. Threaded Elbow	4.00		
209	pcs	1/2"Ø x 1/2"Ø PVC Tee	5.00		
210	pcs	1/2"Ø PVC Coupling	5.00		
211	pcs	1/2"Ø PVC End Cap	3.00		
212	pcs	1/2"Ø PVC Plug	3.00		
213	pcs	1/2"Ø x 1/2"Ø Angle Valve	2.00		
214	pcs	1/2"Ø x 1/2"Ø Two-way Angle Valve	1.00		
215	pcs	1/2"Ø x 1/2"Ø x 16" Flexible Supply Pipe	3.00		



Canvassed By:

SHERMAINE S. UMALI
 Authorized Canvasser

Printed Name / Signature _____
 Tel No. / Cellphone No _____
 TIN No. of Establishment _____
 Date _____

1. Quotations and other requirements stated below shall be submitted to the Civil Aviation Authority of the Philippines - Plaridel Airport Lumang Bayan, Plaridel, Bulacan, Philippines on the date and time stated in this RFQ.

2. Interested bidder/s must submit the following requirements with check (✓) mark:

A. ELIGIBILITY DOCUMENTS

- ✓ Proof of PHICEPS Registration (Registration Number/Certificate). (For ABCs P50K and above)
- ✓ Valid and current Mayor's/Business Permit for CY 2022 OR application for Mayor's/Business Permit with attached Official Receipt (OR) payment of Licensing and Regulatory fees and 2021 Mayor's/Business permit.

B. TECHNICAL AND FINANCIAL DOCUMENTS

- ✓ Duly signed Request for Quotation. Prices shall be quoted in Philippine Pesos. Statement of Compliance must be accomplished by supplier.
- ✓ Valid and current PCAB License (for Infra. and Repair & Maintenance)
- ✓ Latest Income/Business Tax Return (for ABCs above P500K)
- ✓ Duly signed and notarized Omnibus Sworn Statement, using the OPPB prescribed form (for ABCs P50K and above)
- ✓ Original Brochures or certificates of the items offered showing its performance characteristics or specifications, if applicable

Failure to submit all documents as required above shall be automatically be disqualified.

For First time bidder, you are required to submit a portfolio of manpower and equipment.

Price must be inclusive of VAT and must be valid for thirty (30) calendar days from the deadline of submission of quotation.

Ocular Inspection

Upon the decision of the End-User and BAC, the supplier and its concerned premises may be subjected to ocular inspection and approval by the End-User and/or TWG Inspections of the BAC prior to the award

Evaluation of Quotations

Quotations shall be compared and evaluated of the basis of the following criteria:

1. Completeness of Submission
2. Compliance with Item & Description Requirements
3. Price

Award

The supplier that submitted the lowest calculated responsive quotation, and passed the ocular inspection conducted by the End-User and BAC prior to the event, if any, shall be awarded the contract.

Performance Security

Once the Notice of Award of the Project (above 50k) is given the winning bidder is required to submit Performance Security as prescribed by Section 39 of Updated 2016 Revised IRR of RA 9184. to wit:

Form of Performance Security	Amount of Performance Security (Not less than the required percentage of the Total Contract Price)
a) Cash or cashier's/manager's check issued by a Universal or Commercial Bank. For biddings conducted by LGUs, the cashier's/manager's check may be issued by other banks certified by the BSP as authorized to issue such financial instrument. (a)	Infrastructure Projects - Ten percent (10%)
b) Bank draft/guarantee or irrevocable letter of credit issued by a Universal or Commercial Bank. Provided, however, That is shall be confirmed or authenticated by a Universal or Commercial Bank, if issued by a foreign bank. For biddings conducted by LGUs, bank draft/guarantee, or irrevocable letter of credit may be issued by other banks certified by the BSP as authorized to issue such financial instrument. (a)	
c) Surety bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security.	Thirty percent (30%)



Submission of Performance Security will be prior to the signing of the contract.

Non-submission of Performance Security shall warrant disqualification of bids as mandated by Section 40 of Updated 2016 Revised IRR of RA 9184.

Instructions

1. Supplier shall be responsible for the source (s) of its goods/services/equipment, and which shall be in accordance with the schedule and specifications of the RFQ or contract. Failure of the supplier to comply with this provision shall be ground for cancellation of the award or purchase order issued to the supplier.
2. Supplier that accepted an award, purchase order, or contract but failed to deliver the required goods/services/equipment within the time called for in the award, purchase order, or contract shall be disqualified from procurement activities. This is without prejudice to the imposition of other sanctions prescribed under R.A.9184 and its IRR-A against participating in CAAP including all its airports the supplier.
3. All duties, excise, and other taxes, and revenue charges shall be paid by the supplier.
4. All transactions are subject to withholding of credible Government Taxes per revenue regulation(s) of the Bureau of Internal Revenue.

Liquidation Damages

A penalty of one-tenth of one percent (0.001) of the total value of the undelivered goods/services/equipment shall be charged as liquidated damages for every day of delay of the delivery of the Purchased goods/services/equipment.

Warranty

Supplier warrants that all goods/services/equipment to be provided are of acceptable industry standard.

Payment

Payment shall be made only upon a certification by the Head of the Procuring Entity to the effect that the GOODS have been rendered or delivered in accordance with the terms of this Contract and have been duly inspected and accepted.

