



BID BULLETIN No. 017-01

AREA6-PB-2024-017

August 8, 2024

Bid Bulletin No. 017-01, AREA6-PB-2024-017 is hereby issued for the information of Prospective Bidders relative to the bidding for the project ***Repair and Maintenance of Runway Cracks and Potholes Bacolod-Silay Airport.***

1. The ***SCOPE of WORK*** for ***ITEM 3.0: Mobilization*** are as follow:
 - a. Mobilization and De-mobilization process.
 - b. Clean and clear all waste materials.
 - c. All usable and unused materials should turn-over to clients position.
 - d. Shall put-up warning signages during project implementation.

2. The ***ITEMIZED BILL of QUANTITIES*** to be used as part of the ***FINANCIAL COMPONENT ENVELOPE*** for this project is attached hereunder. Revisions in the Itemized Bill of Quantities are **NOT ALLOWED**. Any revisions shall be ground for **DISQUALIFICATION**.

3. The CAAP-BAC AREA6 reserves the right to reject any or all bids, to waive defects or formality therein and to accept bids considered responsive and most advantageous to the Government.

For guidance and information of all concerned.


CHERRY PIE T. ACUÑA

Chairperson

Bids and Awards Committee

Area VI

Civil Aviation Authority of the Philippines





Republic of the Philippines
CIVIL AVIATION AUTHORITY of the PHILIPPINES

ITEMIZED BILL OF QUANTITIES					
PROJECT :		REPAIR and MAINTENANCE of RUNWAY CRACKS and POTHOLES at BACOLOD-SILAY AIRPORT			
LOCATION:		Bacolod-Silay Airport			
ITEM No.	QTY	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
1.0	1	lot	Repair of Runway Potholes		
	200	box	Asphalt Sealant/Oxidize Asphalt 115/15, 25kg box		
	5	pcs	Spade		
	5	pcs	Flat Pry Bar/Bareta		
	5	pcs	Hard Broom Stick		
	5	pcs	Dustpan		
	1	set	Plate Compactor Machine, Engine Motor Operated, Portable, 6HP or more, 100kg or more, 30cm compaction depth.		
	1	set	Concrete/Asphalt Cutter Machine, Max Cut Depth 6inch, 30L water tank capacity, 15Hp or more, Portable		
	5	pcs	Vest, reflectorized, free sizes		
1.1	1	lot	Labor Cost		
1.2	1	lot	Equipment Rental		
2.0	1	lot	Repair of Runway Cracks		
	180	pail	Cold Mix Asphalt 40 kg/pail		
	5	pcs	Spade		
	5	pcs	Flat Pry Bar/Bareta		
	5	pcs	Hard Broom Stick		
	5	pcs	Dustpan		
	5	pcs	Vest, reflectorized, free sizes		
2.1	1	lot	Labor Cost		
2.2	1	lot	Equipment Rental		
3.0	1	lot	Mobilization		





			SCOPE of WORK:		
			1. Mobilization and Demobilization		
			2. Removal of Dirt and Debris along the cracks of the pavement		
			3. Heating of the Blown Asphalt with a Temperature not less than 140 °C to reach the viscosity of the Blown Asphalt.		
			4. Application of the Hot Blown Asphalt to the cracks along the touchdown area of Runway 21 and Runway 03.		
			5. At the completion of the job, remove any additional debris and haul away to avoid the existence of Foreign Object Debris (FOD).		
			6. The Selected bidder (“contractor”) is required to carry out all necessary site investigations for the repair of runway.		
			7.The Contractor shall carry out all the works using their own material, labour, equipment and mix design		
			8.The contractor should have expertise and resources in delivering the services required in the Scope of Works.		
			9.The Contractor shall exercise good workmanship and all the Works shall be completed to the satisfaction of CAAP BSA		
PROJECT COST					₱

Name of Bidder: _____

Name: _____

Legal Capacity: _____

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____

Date: _____

