



21 October, 2024 Date

REQUEST FOR QUOTATION

Sir/Madam:

Please quote your lowest net prices, taxes, including Government discount terms, and period of delivery of the following items listed hereunder for the account of the official use of the Civil Aviation Authority of the Philippines (CAAP), Area Center V, in connection with the implementation of the Emission Testing Of Diesel Engine Generator Set (DEG'S) At Bicol International Airport project. It is requested that price quotations be submitted in an envelope, duly sealed, to be opened by our Canvass and Contract Committee (CCC) not later than 2:00 p.m. on 25 October 2024 at the CAAP's physical address at the BAC/CCC Office, Ground Floor, Admin Bldg., Bicol International Airport (BIA), Daraga, Albay.

ITEM			DESCRIPTION		
ITEM	UNIT	QTY.	(LOCATION: BIA, DARAGA,	UNIT PRICE	TOTAL
NO.			ALBAY)		
	lan		Emission Test of 3MVA DEGS #1,		
1.	lot	1	DEGS #2 and 250 KVA DEGS #3		
	9	l.) Insta	llation of Smoke Stack Ports		
			a.) Source: 3MVA DEGS #1 (Twin		
			smoke stack - Left and Right)		
			Work Description: Installation of		
			smoke stack extension and		
			sampling ports for twin stack		
			b.) Source: 3MVA DEGS #2 (Twin		
			smoke stack - Left and Right)		
			Work Description: Installation of		
		*	smoke stack extension and		
			sampling ports for twin stack		
			c.) Source: 250KVA (Single smoke		
			stack)		
			Work Description: Installation of		
			smoke stack extension and		
			sampling ports for single stack		







ITENA			DESCRIPTION		
ITEM	UNIT	QTY.	(LOCATION: BIA, DARAGA,	UNIT PRICE	TOTAL
NO.			ALBAY)		
Contin	uation				
		II Samni	ing and Analysis		
		ii. Sairipi	ing and Analysis		
			Source: 3MVA DEGS #1 (Twin		
			smoke stack - Left and Right)		
			a.) Parameters: Particulate Matter		
			(PM) Sulfur Oxides (Sox) Nitrogen		
	1		Oxides (Nox) Carbon Monoxide		
1			(CO).		
F		1	Testing Duration: 6 to 7 hours for		
			the Left smoke stack and 6 to 7		
			hours for the Right smoke stack.		
			Source: 3MVA DEGS #2 (Twin		
			smoke stack - Left and Right)		
			b.) Parameters: Particulate Matter		
			(PM) Sulfur Oxides (Sox) Nitrogen		
			Oxides (Nox) Carbon Monoxide		
			(CO).		
			Testing Duration: 6 to 7 hours for		
			the Left smoke stack and 6 to 7		
			hours for the Right smoke stack.		
			Source: 250KVA (Single smoke		
			stack)		
			c.) Parameters: Particulate Matter		
			(PM) Sulfur Oxides (Sox) Nitrogen		
			Oxides (Nox) Carbon Monoxide		
			(CO).		
			Testing Duration: 6 to 7 hours.		
	An		TOTAL AMOUNT OF	QUOTATION	
			-x-x- nothing follows -x-x-		
			A A Hothing Johons A A		





Quotations not accompanied by current Mayor's/Business Permit; Phil-GEPS Registration Number; and List of completed similar project shall be automatically disqualified. Your prices must be quoted in Philippine Peso and must include the unit price and total price, inclusive of all taxes to be paid and other incidental cost to the delivery site if the contract is awarded.

Quotations will be opened in the presence of the Bidders' representatives who choose to attend at the address below.

Quotations must be delivered to the Civil Aviation Authority of the Philippines, Area Center V at its physical address at the BAC/CCC Office, Ground Floor Admin Bldg., Bicol International Airport, Daraga, Albay not later than 2:00 p.m. on 25 October 2024.

Online submission is not allowed and late quotations shall not be accepted. All quotations together with the required documents should be placed in a sealed envelope marked Emission Testing Of Diesel Engine Generator Set (DEG'S) At Bicol International Airport.

TERMS OF REFERENCE

Name of Project	Emission Testing Of Diesel Engine Generator Set (DEG'S) At Bicol International Airport
Approved Budget	Eight Hundred Thirty Thousand Pesos (Php 830,000.00)
Number of Days to Complete	Thirty (30) calendar days.
Location/s	Bicol International Airport, Naga Airport, Masbate Airport & Virac Airport.







	The Contractor shall carry out the works properly and in accordance with the Contract. The Contractor shall provide all supervision, labor, materials, plant and equipment required for the project.
the receipt of Notice to Pr with the Contract Agreem	2. The Contractor shall commence execution of the works immediately upon the receipt of Notice to Proceed and shall carry out the works in accordance with the Contract Agreement. The Contractor shall complete the project per approved Contract time of Thirty (30) calendar days.
Obligation	3. The Contractor shall be responsible for the safety of all activities on the Site.
	4. The Contractor shall carry out all instructions of the Procuring Entity's Representative that comply with the applicable laws where the Site is located.
Liquidated Damages	The Contractor shall pay liquidated damages to the Procuring Entity at the rate per day of delay. The applicable liquidated damages is at least one tenth (1/10) of one percent of the cost of the unperformed portion for every day of delay.

Canvass and Contract Committee







EPIFANIO O. PRINIA, JR.

Chairperson, Canvass and Contract Committee Civil Aviation Authority of the Philippines Bicol International Airport Daraga, Albay

Sir:

In connection with the above Request for Quotation, I/We propose to furnish deliver in conformity with specification of the articles in which I/We quoted, and insofar as controlled items are concerned, the price quotation I/We have made in accordance with those approved by the Price Control Council.

Signature Over Pri	nted Name of D	ealer/Supplier
_		

TO WHOM IT MAY CONCERN:

This is to certify that I have personally served this Request for Quotation for the project **Emission Testing Of Diesel Engine Generator Set (DEG'S) At Bicol International Airport** to the abovenamed dealer/supplier in accordance with the existing regulations.



