



Republic of the Philippines CIVIL AVIATION AUTHORIT

F THE PHILIPPINES

Date: lune 3, 2025

REQUEST FOR QUOTATION NO.: RFQ-2025-045

| Name of the Company | : | |
|---------------------------|---|--|
| Address | : | |
| Contact No. | : | |
| PhilGEPS Registration No. | : | |

Sir/Madam:

Please quote your best offer (lowest net, price, taxes, and government discount terms included) and **submit your Quotation duly signed by you or your duly authorized representative not later than June 9, 2025 @ 10:00 AM for:**

Name of the

the : CONSTRUCTION OF CHILD MINDING CENTER AT LAOAG

Project

INTERNATIONAL AIRPORT

Location

LAOAG INTERNATIONAL AIRPORT

Terms

of :

Reference

Sealed quotations must be submitted either personally to Ms. Josephine R. Flores, Head, Secretariat of the Bids and Awards Committee of CAAP Area I (BAC Area I) or e-mail at bac_area1@caap.gov.ph. For any clarification, do not hesitate to contact us through the contact information seen below.

Aside from the Terms and Conditions provided at the back portion of this RFQ, please observed the following general conditions:

- 1. The following documents must be attached upon submission of the Quotation:
 - a) Mayor's Permit
 - b) PhilGEPS Certificate of Registration
- 2. All quotations shall be considered as fixed price and not subject to price escalation during the contract implementation.
- 3. Payment shall be made through check.

ATTY. RIZZA JOY'S. VALLESTERO

Chairperson, Bids and Awards Committee

After having carefully read and accepted the Terms and Conditions, I/We submit our quotations for the following item/s:

| ITEM DESCRIPTION | APPROVED | | | | OFFER* | | | |
|-------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|-----|------|---------------|-------------|------|--------------------------------|---------|
| (SPECIFY THE BRAND AND MODEL OF YOUR | BUDGET OF THE CONTRACT | | | PRICE | | Tecl | iance w/ nnical ications | REMARKS |
| OFFER/PROPOSAL, IF APPLICABLE) | (ABC) | QTY | UNIT | Unit Price | Total Price | Yes | No | |
| 1. Supply of materials, equipment and labor for the project titled: "Construction of Child Minding Center at Laoag International Airport" | ₱1,999,922. 48 | 1 | lot | | | | | |







| | | | | The second | |
|-----------------------------|-------------|--|--|------------|--|
| SCOPE OF WORKS: | | | | | |
| 1. Site Works | | | | | |
| 2. Concrete Works | | | | | |
| 3. Masonry Works | | | | | |
| 4. Roofing Works | | | | | |
| 5. Ceiling Works | | | | | |
| 6. Painting Works | | | | | |
| 7. Tiling Works | | | | | |
| 8. Cladding Works | | | | | |
| 9. Plumbing Works | | | | | |
| 10. Electrical Works | | | | | |
| 11. Doors & Partition Walls | | | | | |
| 12. Other General | | | | | |
| Requirements | | | | | |
| 13. Project Billboard | | | | | |
| TOTAL ABC | ₱1,999,922. | | | | |
| TOTAL ABC | 48 | | | | |
| GRANI | TOTAL: | | | | |
| | | | | | |

Note: Quotation for each item must not exceed the ABC per item. This is a one (1) lot procurement.

> Signature over Printed Name Supplier/Dealer/Contractor





TERMS AND CONDITIONS

- Bidders shall provide correct and accurate information required in this form.
- Price quotation/s must be valid for a period of Thirty (30) calendar days from the date of submission.
- 3. Price quotation/s shall be denominated in Philippine Peso which includes all taxes, duties and/or levies payable.
- 4. Quotations exceeding the ABC shall be rejected.
- 5. Award of contract shall be made to the lowest quotation (for goods and infrastructure) or, the highest rated offer (for consulting services) which complies with the minimum technical specifications and other terms and conditions stated herein. Further, the most advantageous to the government to the point of quality of materials and prices as well as the responsiveness of the bids shall be the basis of the award.
- The Head of the Procuring Entity reserves the right to reject any and all bids, declare a failure of bidding or not award the contract in any of the following conditions set forth by Sec. 41 (Reservation Clause) of the Revised IRR of RA 9184.
- The Supply Office of LIA shall have the right to inspect and to test the goods to confirm their conformity to the technical specifications.
- Date of Completion/Delivery: In case of an approved POW, within the period stated therein. While, in cases of regular procurement, within 7-10 days or less, after the issuance of the Purchase Order. Further, any request of extension shall be sent to the End-User/Implementing Facility concern.
- Mode and Terms of Payment: Within ten (10) working days after the supplies/materials and labor/service have been inspected and accepted, respectively, through a check issued by the procuring entity.
- 10. Liquidated damages equivalent to one tenth of one percent (0.001%) of the value of the goods not delivered within the prescribed delivery period shall be imposed per day of delay. This Office (LIA) shall rescind the contract once the cumulative amount of liquidated damages reaches ten percent (10%) of the amount of the contract, without prejudice to other courses of action and remedies open to it.

NOTE: The aforecited Terms and Conditions shall be without prejudice to any provisions of a Contract which will be executed by and between the Procuring Entity and Contractor/Supplier/Dealer in order to conform with the requirements set forth by RA 9184.







SITE WORKS

Quantity:

60.8525 cu.mtr. (Including demolition, excavation, backfilling and gravel bedding works)

A. **DIRECT COST**

| a. | MATERIALS | | MATERIALS QUANTITY U | | UNIT COST | AMOUNT |
|----|--------------------------|----|----------------------|---------|-----------|--------|
| 1 | Aggregate Subbase Course | 34 | cu.m. | cu.m./ | | |
| 2 | G1, Gravel Bedding | 7 | cu.m. | cu.m./ | | |
| | | | MATERIA | AL COST | | |

|). | EQUIPMENT | | EQUIPMENT QUANTITY | | UNIT COST | AMOUNT |
|----|-----------|-------------------|--------------------|---------|-----------|--------|
| 1 | 1 | Demolition Hammer | 4 | day | day/ | |
| 2 | 1 | Concrete Cutter | 4 | day | day/ | |
| 3 | 1 - | Plate Compactor | 2 | day | day/ | |
| | | | | EQUIPME | NT COST | |

| :. | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|----|--------------------|----------------|-----|---------|-----------|--------|
| 1 | 1 | Foreman | 6 | day | day/ | |
| 2 | 4 | Common Laborer | 6 | day | day/ | |
| | | | | LABOR | COST | |

| TOTAL DIRECT COST | |
|-------------------|--|
| TOTAL DIRECT COST | |

INDIRECT COST B.

| a. OCM(Overhead, Contingencies, Miscellaneous | | |
|------------------------------------------------|---------------|--|
| b. CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

| C. Value Added Tax, VAT (OCM + Contractor's Profit + Direct Cost) | 5% | |
|-------------------------------------------------------------------|----|--|

TOTAL INDIRECT COST

TOTAL COST C.

| a. DIRECT COST + INDIRECT COST | |
|--------------------------------|--|





II. CONCRETE WORKS

/ Quantity:

18.32 cu.m.

A. DIRECT COST

| | MATERIALS | QUA | NTITY | UNIT COST | AMOUNT |
|----|----------------------|-----|----------|-----------|--------|
| 1 | Portland Cement 40kg | 169 | bag | /bag | |
| 2 | Course Aggregate | 19 | cu. mtr. | /cu. mtr. | |
| 3 | Fine Aggregate | 10 | cu. mtr. | /cu. mtr. | |
| 4 | 1/2" Phenolic Board | 10 | pc. | /pc. | |
| 5 | 16mm RSB @ 7.5m | 52 | pc. | /pc. | |
| 6 | 16mm RSB @ 6m | 38 | pc. | /pc. | |
| 7 | 12mm RSB | 127 | pc. | /pc. | |
| 8 | 10mm RSB | 113 | pc. | /pc. | |
| 9 | #16 G.I. Tie Wire | 3 | roll | /roll | |
| 10 | Assorted CWN | 5 | kg. | /kg. | |
| 11 | 2" x 2" Good Lumber | 305 | bd. Ft. | /bd. Ft. | |
| | | | MATERIA | AL COST | |

|). | no. of units | EQUIPMENT | QUANTITY | | UNIT COST | AMOUNT |
|----|--------------|-------------------|----------|---------|-----------|--------|
| 1 | 1 | One Bagger Mixer | 5 | day | day/ | |
| 2 | 1 | Concrete Vibrator | 5 | day | day/ | |
| 3 | 20 | Scaffolding | 28 | days | days/ | |
| | | | | EQUIPME | NT COST | |

| | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|---|--------------------|-----------------|-----|---------|-----------|--------|
| 1 | 1 | Foreman | 21 | day | day/ | |
| 2 | 2 | Skilled Laborer | 21 | day | day/ | |
| 3 | 3 | Common Laborer | 21 | day | day/ | |
| | | | | LABO | | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscellane | | |
|---------------------------------------------|---------------|--|
| b. CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

| | | , | |
|----------------------------------------------------------------|----|---|--|
| C. alue Added Tax, VAT (OCM + Contractor's Profit + Direct Cos | 5% | | |

TOTAL INDIRECT COST

C. TOTAL COST

| a. DIRECT COST + INDIRECT COST | |
|--------------------------------|--|
| | |
| | |
| | |
| | |





III. MASONRY WORKS

/ Quantity:

167 sq.m.

A. DIRECT COST

| a. | | MATERIALS | QUAI | YTITY | UNIT COST | AMOUNT |
|----|---|----------------------|------|----------|-----------|--------|
| | 1 | Portlant Cement 40kg | 165 | bag | /bag | |
| | 2 | 5" CHB | 1659 | pcs | /pcs | |
| | 3 | 4" CHB | 420 | pcs | /pcs | |
| | 4 | Fine Aggregate | 19 | cu. mtr. | /cu. mtr. | |
| | 5 | 12mm RSB | 94 | pc. | /pc. | |
| | 6 | #16 G.I. Tie Wire | 1 | roll | /roll | |
| | 7 | Concrete Epoxy | 1 | set | /set | |
| L | | | | MATER | IAL COST | |

| b. | | no. of units | EQUIPMENT | QUAN | YTITY | UNIT COST | AMOUNT |
|----|---|--------------|----------------------|------|---------|-----------|--------|
| | 1 | 8 Re | ental of Scaffolding | 10 | day | day/ | |
| _ | | | | | EQUIPMI | ENT COST | |

| | no. of manpower | LABOR | NO. C | F DAYS | UNIT COST | AMOUNT |
|---|--------------------|----------------|-------|--------|-----------|--------|
| 1 | 1 | Foreman | 14 | day | day/ | |
| 2 | 2 | Mason | 14 | day | day/ | |
| 3 | 4 | Common Laborer | 14 | day | day/ | |
| | | | | LABO | R COST | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. | OCM(Overhead, Contingencies, Miscellane | | |
|----|------------------------------------------|---------------|--|
| b. | CONTRACTORS PROFIT | | |
| | | TOTAL MARK-UP | |
| | , | | |

| C. alue Added Tax, VAT (OCM + Contractor's Profit + Direct Cos | 5% | |
|----------------------------------------------------------------|----|--|

TOTAL INDIRECT COST

C. TOTAL COST

| a. DIRECT COST + INDIRECT COST | | |
|--------------------------------|--------------------------------|--|
| | a. DIRECT COST + INDIRECT COST | |





IV. ROOFING WORKS

/ Quantity:

65 sq. mtr.

A. DIRECT COST

| | MATERIALS | QUA | NTITY | UNIT COST | AMOUNT |
|----|---------------------------------------|-----|----------|-----------|--------|
| 1 | Pre-painted Rib type roofing (0.50mm) | 65 | sq. mtr. | /sq. mtr. | |
| 2 | 1.2mm x 2" x 4" C-Purlins | 8 | pc. | /pc. | |
| 3 | 12 x 55 Tekscrew | 720 | рс | /pc | |
| 4 | Fabricated Gutter 0.60mm x 24" | 16 | pc. | /pc. | |
| | 1.2m x 2.4m x 0.60 mm Pre-painted Gl | | | | |
| 5 | Sheet | 9 | pc. | /pc. | |
| 6 | Welding Rod | 12 | kg | /kg | |
| 7 | φ10mm x 6m Sag Rods | 10 | pc. | /pc. | |
| 8 | Silicone Rubber Sealant | 6 | pc. | /pc. | |
| 9 | Insulation Foam (10mm Double, 30m) | 2 | pc. | /pc. | |
| 10 | 50mm x 50mm x 4mm x 6m Angle Bar | 24 | pc. | /pc. | |
| 11 | Red Oxide Primer | 2 | gals | /gals | |
| 12 | Enamel Paint | 2 | gals | /gals | |
| - | Paint Thinner | 2 | liter | /liter | |
| | 4" Paint Brushes/Rollers | 5 | pcs. | /pcs. | |
| | | | MATERIA | L COST | |

|). | no. of units | EQUIPMENT | QUA | NTITY | UNIT COST | AMOUNT |
|----|--------------|-----------------|----------------|-------|-----------|--------|
| 1 | 1 | Welding Machine | 3 | day | day/ | |
| 2 | 8 | Scaffolding | 7 | day | day/ | |
| | | | EQUIPMENT COST | | | |

| :. | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|----|--------------------|-----------------|-----|---------|-----------|--------|
| 1 | 1 | Foreman | 7 | day | day/ | |
| 2 | 2 | Skilled Laborer | 7 | day | day/ | |
| 3 | 2 | Common Laborer | 7 | day | day/ | |
| | | | | LABOR | COST | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscellaneou | | |
|-----------------------------------------------|---------------|--|
| b. CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

| C. Value Added Tax, VAT (OCM + Cor | ntractor's Profit + Direct Cost) | 5% | |
|------------------------------------|----------------------------------|----|--|
| | | | |

TOTAL INDIRECT COST

C. TOTAL COST





| a. DIRECT COST + INDIRECT COST | - |
|--------------------------------|---|





V. CEILING WORKS

/ Quantity:

55 sq.m.

A. DIRECT COST

| a. | | MATERIALS | QUA | NTITY | UNIT COST | AMOUNT |
|----|---|-----------------------------------------|-----|---------|-----------|--------|
| | 1 | Double Furring Channel | 55 | pc. | /pc. | |
| | 2 | Wall Angle | 15 | pc. | /pc. | |
| | 3 | Blind Rivet | 3 | boxes | /boxes | |
| | 4 | PVC Ceiling Panel 1.2x215x2950mm | 64 | pc. | /pc. | |
| | 5 | PVC Ceiling Panel accessories H-profile | 4 | pc. | /pc. | |
| | 6 | PVC Ceiling Panel accessories U-Clip | 16 | pc. | /pc. | |
| | 7 | 12mm x 1' x 8ft. Senepa | 4 | pc. | /pc. | |
| | 8 | M8 x 50mm Metal Expansion Bolts | 40 | pcs | /pcs | |
| | 9 | Self-Drilling Tek Screws (12mm) | 760 | pcs | /pcs | |
| | | Silicone Rubber Sealant | 2 | рс | /pc | |
| _ | | | | MATERIA | AL COST | |

| b. | no. of units | EQUIPMENT | QUA | NTITY | UNIT COST | AMOUNT |
|----|--------------|-------------|-----|---------|-----------|--------|
| 1 | | Scaffolding | 7 | day | day/ | |
| | | | | EQUIPME | NT COST | |

| | no. of manpower | LABOR | NO. OF DAYS | | UNIT COST | AMOUNT |
|---|-----------------|-----------------|-------------|-----|-----------|--------|
| 1 | | Foreman | 7 | day | day/ | |
| 2 | 2 | Skilled Laborer | 7 | day | day/ | |
| 3 | 2 | Common Laborer | 7 | day | day/ | |
| | | | LABOR COST | | | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscellaneous | | |
|------------------------------------------------|---------------|--|
| b. CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

| C. Value Added Tax, VAT (OCM + Contractor's Profit + Direct Cost) | 5% | |
|-------------------------------------------------------------------|----|--|

TOTAL INDIRECT COST

C. TOTAL COST

a. DIRECT COST + INDIRECT COST





VI. PAINTING WORKS

Quantity:

183.5 sq.m.

A. DIRECT COST

| ı. 🗆 | MATERIALS | QUA | NTITY | UNIT COST | AMOUNT |
|------|--------------------------|-----|---------|-----------|--------|
| 1 | Acrylic Semi-Gloss Latex | 15 | gals | /gals | |
| 2 | Paint Roller 9" w/ Tray | 4 | pc. | /pc. | |
| 3 | Paint Brush 4" | 8 | pc. | /pc. | |
| 4 | Masonry Putty | 8 | gals | /gals | |
| 5 | Sand paper | 10 | pcs | /pcs | |
| 6 | Elastomeric Sealant | 4 | pails | /pails | |
| 7 | Putty Knife | 6 | pcs | /pcs | |
| | | | MATERIA | L COST | |

| b. | no. of units | EQUIPMENT | QUA | NTITY | UNIT COST | AMOUNT |
|----|--------------|-------------|-----|---------|-----------|--------|
| 1 | 8 | Scaffolding | 5 | day | day/ | |
| | | | | EQUIPME | NT COST | |

| | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|---|--------------------|----------------|------------|---------|-----------|--------|
| 1 | 1 | Foreman | 5 | day | day/ | |
| 2 | 2 | Painter | 5 | day | day/ | |
| 3 | 2 | Common Laborer | 5 | day | day/ | |
| | | | LABOR COST | | | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscellaneou | | |
|-----------------------------------------------|---------------|--|
| b. CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

| C. | Value Added Tax, VAT (OCM + Contractor's Profit + Direct Cost) | 5% | |
|----|----------------------------------------------------------------|----|--|

TOTAL INDIRECT COST

C. TOTAL COST

a. DIRECT COST + INDIRECT COST





VII. TILING WORKS

/ Quantity:

102.049 sq.m.

A. DIRECT COST

| | MATERIALS | QUANTITY | | UNIT COST | AMOUNT |
|---|-------------------------------------------|----------|---------|-----------|--------|
| | 30cm x 30cm Matte Rustic Tiles, Material: | | | | |
| 1 | Ceramic, Color: White Sugar Finish | 105 | pc. | /p | oc. |
| | 30cm x 60cm Matte Finish, Material: | | | | |
| 2 | Ceramic, Color: Viene Ash | 115 | pc. | /p | oc. |
| | 60cm x 120cm Matte Rustic Tiles, | | | | |
| | Material: Porcelain, Color: Vernia White, | | | | |
| 3 | Edge: Rectified | 70 | pc. | /p | oc. |
| | 30cm x 30cm Matte Rustic Tiles, Material: | | | | |
| 4 | Ceramic, Color: Taupe (Gray) | 300 | pc. | /p | c. |
| 5 | Tile Adhesive | 12 | bags | /ba | ags |
| 6 | Tile Grout | 52 | kg | /k | g |
| 7 | Cement | 9 | bags | /ba | ags |
| 8 | 4" Diamond Cutting Disc | 2 | pc. | /p | c. |
| | | | MATERIA | L COST | |

| b. | no. of units | no. of units EQUIPMENT | | QUANTITY | | AMOUNT |
|----|--------------|------------------------|---|----------|---------|--------|
| 1 | 1 | Angle Grinder | 8 | day | day/ | |
| | | | | EQUIPME | NT COST | |

| | no. of manpower | LABOR | | OF DAYS | UNIT COST | AMOUNT |
|---|--------------------|----------------|---|---------|-----------|--------|
| 1 | 1 | Foreman | 8 | day | day/ | |
| 2 | 2 | Tile Setter | 8 | day | day/ | |
| 3 | 2 | Common Laborer | 8 | day | day/ | |
| | | | | LABOR | COST | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscellaneous) | | |
|-------------------------------------------------|---------------|--|
| b. CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

| c. | Value Added Tax, VAT (OCM + Contractor's Profit + Direct Cost) | 5% | |
|----|----------------------------------------------------------------|----|--|
| | | | |

TOTAL INDIRECT COST

C. TOTAL COST

| a. DIRECT COST + INDIRECT COST | |
|--------------------------------|--|
| a. DIRECT COST + INDIRECT COST | |





TOTAL UNIT COST

₽





VIII. CLADDING WORKS

| and the second | and the second s | | 77 |
|----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|
| 1 | Quantity: | 1 | lot |

A. DIRECT COST

| a. | | MATERIALS | QUANTITY | | UNIT COST | AMOUNT |
|----|----|----------------------------------------------|----------|---------|-----------|--------|
| | | 4' x 8' x 3mm Al. thickness Aluminum | | | | |
| | 1 | Composite Panel | 31 | pcs | /pcs | 3 |
| | 2 | 2" x 3" x 1.2mm Tubular | 10 | pcs | /pcs | 3 |
| | 3 | 1" x 2" x 1.0mm Tubular | 10 | pcs | /pcs | 3 |
| | 4 | 1" x 1" x 1.0mm Tubular | 2 | pcs | /pcs | 5 |
| | 5 | Bracket (Angle Bar) | 100 | pcs | /pcs | 3 |
| | 6 | 4mmx32mmx32mm Angle Bar | 6 | pcs | /pcs | 3 |
| | 6 | Screw | 200 | pcs | /pcs | 5 |
| | 7 | Rivet | 3 | boxes | /boxe | es |
| | 8 | 15mm x 50 meters PE Foam Backer Rod Stick | 3 | rolls | /roll | S |
| | 9 | Rubber Sealant | 30 | tubes | /tube | es . |
| | 10 | 202mmx30mmx2.85m WPC Indoor Panel | 40 | pcs | /pcs | ; |
| | 11 | 224x26x2900mm WPC Outdoor Cladding | 13 | pcs | /pcs | 5 |
| | 12 | Expansion Bolt | 60 | pcs | /pcs | 5 |
| | 13 | Welding Rod | 5 | kg | /kg | |
| _ | | Stainless 304 Flat Lettering | 18 | units | /unit | S |
| | | | | MATERIA | AL COST | |

| | no. of units | no. of units EQUIPMENT | | NTITY | UNIT COST | AMOUNT |
|---|--------------|------------------------|----|---------|-----------|--------|
| 1 | 8 | Scaffolding | 8 | day | day/ | |
| 2 | 1 | Hand Router | 8 | day | day/ | |
| 3 | 1 | Welding Machine | 10 | day | day/ | |
| | J | ŭ . | | EQUIPME | NT COST | |

| | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|---|--------------------|-----------------|-----|---------|-----------|--------|
| 1 | 1 | Foreman | 10 | day | day/ | |
| 2 | 2 | Skilled Laborer | 10 | day | day/ | |
| 3 | 2 | Common Laborer | 10 | day | day/ | |
| | | | | LABOR | COST | |

TOTAL DIRECT COST

B. INDIRECT COST

Value Added Tax, VAT (OCM + Contractor's Profit + Direct Cost)

| TOTAL MARK-UP |
|---------------|
| |

5%





TOTAL INDIRECT COST

C. TOTAL COST

| a. DIRECT COST + INDIRECT COST | - |
|--------------------------------|---|
| a. DIRECT COST + INDIRECT COST | |

TOTAL UNIT COST

€





IX. PLUMBING WORKS

| / | Quantity: | 1 | lot |
|---|-----------|---|-----|
| | | | |

A. DIRECT COST

| | MATERIALS | | NTITY | UNIT COST | AMOUNT |
|----|------------------------------------|----|-------|-----------|--------|
| | PVC Vanity Wall Hung Cabinet w/ | | | | |
| 1 | Reflective Mirror | 1 | unit | /unit | |
| 2 | One Piece Skirted Water Closet | 1 | unit | /unit | |
| | 350x380x750mm Urinal with | | | | |
| 3 | Sensor | 1 | unit | /unit | |
| 4 | Lavatory Faucet | 1 | unit | /unit | |
| 5 | 2000L Pp/Pe Septic Tank | 1 | unit | /unit | |
| | Angle Valve 1x1 Stainless Steel | | | | |
| 6 | 304 | 2 | pcs | /pcs | |
| | Angle Valve 1x2 Stainless Steel | | | | |
| 7 | 304 | 1 | pcs | /pcs | |
| 8 | PPR Coupling Reducer 3/4" x 1/2" | 2 | pcs | /pcs | |
| 9 | PPR Coupling 3/4" | 4 | pcs | /pcs | |
| 10 | PPR Elbow Threaded 20mm dia. | 2 | pcs | /pcs | |
| 11 | PPR Elbow Plain 20mm dia. | 5 | pcs | /pcs | |
| 12 | PPR Elbow Plain 25mm dia. | 7 | pcs | /pcs | |
| 13 | PPR Tee Plain 25mm dia. | 6 | pcs | /pcs | |
| 14 | PPR PN20mm dia. | 2 | pcs | /pcs | |
| 15 | PPR PN25mm dia. | 4 | pcs | /pcs | |
| | Handspray Bidet Stainless Steel | | | | |
| 16 | 304 Satin Finish | 1 | pcs | /pcs | |
| | Flexible Connector 1/2" dia. X16" | | | | |
| 17 | Stainless Steel 304, Satin Finish | 3 | pcs | /pcs | |
| | Sanitary Pipe 4" Dia. Orange | | | | |
| 18 | Series 1000 | 5 | pcs | /pcs | |
| | Sanitary Pipe 2" Dia. Orange | | | | |
| 19 | Series 1000 | 2 | pcs | /pcs | |
| 20 | Wye Plain Sch. 40 Sanitary 4" dia. | 4 | pcs | /pcs | |
| 21 | Sanitary Elbow 90° x 4" | 3 | pcs | /pcs | |
| 22 | | 2 | pcs | /pcs | |
| 23 | Sanitary Elbow 2" | 10 | pcs | /pcs | |
| 24 | Sanitary P-Trap 2" | 4 | pcs | /pcs | |
| | Floor Drain Stainless Steel 304 | | | | |
| 25 | Satin Finish | 2 | pcs | /pcs | |
| 26 | Solvent Cement 200ml | 1 | can | /can | |
| | Wall Tap Faucet (Material: Zinc | | | | |
| 27 | Alloy) | 2 | рс | /pc | |
| | Polished Tissue Holder Stainless | | | | |
| 28 | 304 | 1 | unit | /unit | |
| | Jumbo Roll Paper Towel JRT | | | | |
| 29 | Stainless Dispenser Wall Mounted | 1 | unit | /unit | |





Republic of the Philippines

CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

| | BAGONG PILIPINAS | | | | · | | |
|----|--------------------------|----------|---|------|-----------|------|--|
| | 120x23.5x3.8cm Modern | Floating | | | | | |
| | Shelves/ Ledge; Material | Medium | | | | | |
| 30 | Density Fiberboard | | 8 | pcs | | /pcs | |
| | | | | MATE | RIAL COST | | |

| b. | no. of units | EQUIPMENT | QUANTITY | UNIT COST | AMOUNT |
|----|--------------|-----------|----------|-----------|--------|
| | | | EOUIPN | MENT COST | |

| | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|---|--------------------|-----------------|-----|---------|-----------|--------|
| 1 | 1 | Foreman | 4 | day | day/ | |
| 2 | 2 | Skilled Laborer | 4 | day | day/ | |
| 3 | 2 | Common Laborer | 4 | day | day/ | |
| | | | | LABO | R COST | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscell | | |
|------------------------------------------|---------------|--|
| b. CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

| C. Je Added Tax, VAT (OCM + Contractor's Profit + Direct Co | 5% | 5 | |
|-------------------------------------------------------------|----|---|--|

TOTAL INDIRECT COST

C. TOTAL COST

| a. DIRECT COST + INDIRECT COST | |
|--------------------------------|--|
|--------------------------------|--|





IX. ELECTRICAL WORKS

| 1 | Quantity: | 1 | lot |
|---|------------|---|-----|
| / | Qualitity. | 1 | 101 |

A. DIRECT COST

| | MATERIALS | QUAI | QUANTITY | | COST | AMOUNT |
|----|----------------------------------------------------------------------------|------|----------|--------|---------|--------|
| 1 | 300mmx1200mm Recessed Panel Light 48w | 8 | set | | /set | |
| 2 | Pin Lights LED Bulb Concealed 6"x12Watts | 18 | set | 1000 | /set | |
| 3 | 2-Gang Switch Wide Series | 5 | set | | /set | |
| 4 | 3.5 sq.mm. THHN Wire (150m) | 2 | set | | /set | |
| 5 | 2.0 sq.mm. THHN Wire (150m) | 2 | box | | /box | |
| 6 | ACU Outlet | 3 | box | | /box | |
| | HD Outlet | 1 | set | | /set | |
| 8 | Duplex Universal Convenience Outlet with Weatherproof Plate Cover | 6 | set | | /set | |
| 9 | Utility Box PVC | 16 | set | | /set | |
| 10 | Junction Box (Octagonal 9x9) | 26 | pcs | | /pcs | |
| 11 | Panel Board (10 Holes w/ Center Main) | 1 | pcs | | /pcs | |
| 12 | Breaker: 15AT CB 2P, Bolt on MCCB | 3 | set | | /set | |
| 13 | Breaker: 20AT CB 2P, Bolt on MCCB | 4 | pcs | | /pcs | |
| 14 | Breaker: 30AT CB 2P, Bolt on MCCB | 4 | pcs | | /pcs | |
| 15 | Breaker:70AT CB 2P, Bolt on MCCB | 1 | pcs | | /pcs | |
| 16 | 22 sq.mm. THHN Wire | 20 | meters | | /meters | |
| 17 | NEMA 3R 70AT CB Bolt on 2P | 1 | set | | /set | |
| 18 | 20mm dia. Sch 40 Thk Wall Orange Pipe | 32 | pcs | | /pcs | |
| 19 | 32mm dia. Sch 40 Thk Wall Orange Pipe | 14 | pcs | | /pcs | |
| | Electrical Tape Big | 5 | pcs | | /pcs | |
| 21 | 12-Inch Wall Mounted Exhaust Fan | 1 | pcs | | /pcs | |
| 22 | 315.8x140x101.1mm Emergency Light w/ Injection Moulded Abs Plastic Housing | 4 | pcs | | /pcs | |
| - | | | MATERIA | L COST | | |

| b. | | no. of units | EQUIPMENT | QUA | NTITY | UNIT COST | AMOUNT |
|----|---|--------------|-------------|-----|---------|-----------|--------|
| | 1 | 1 | Scaffolding | 4 | day | day/ | |
| _ | | | | | EQUIPME | NT COST | |

| m | no. of nanpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|---|--------------------|-------------|-----|---------|-----------|--------|
| 1 | 1 | Foreman | 4 | day | day/ | |
| 2 | 1 | Electrician | 4 | day | day/ | |
| | | | | LABOR | COST | |

TOTAL DIRECT COST





B. INDIRECT COST

| OCM(Overhead, Contingencies, Miscellaneous) | | |
|----------------------------------------------|---------------|--|
| . CONTRACTORS PROFIT | | |
| | TOTAL MARK-UP | |

TOTAL INDIRECT COST

C. TOTAL COST

| a. | DIRECT COST + INDIRECT COST | |
|----|-----------------------------|--|





IX. DOORS AND PARTITION WALLS

| 1/1. | DOORSAN | | 111011 1111220 | | | |
|------|-----------|---|----------------|--|--|--|
| / | Quantity: | 1 | _lot | | | |
| | | | | | | |

A. DIRECT COST

| a. | | | QUA | NTITY | UNIT COST | AMOUNT |
|----|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|-----------|--------|
| | 1 | 2100mm x 1800 mm, 1/2" Tempered Glass Double Swing Door (Frameless, Complete with door closer, stainless steel door handle - H-Type) | 1 | unit | /uni | |
| | 2 | 2100mm x 900 mm, 1/2" Tempered Glass Swing Door (Frameless, Complete with door closer, stainless steel door handle) | 1 | unit | /uni | |
| | 3 | 2100mm x 800mm Single Leaf PVC Moulded Door (Complete with 4pc. Ball Bearing hinge, Lever type (zinc alloy) Single cylinder deadbolt, Plain Matte Finish Gray) | 2 | unit | /uni | |
| | 4 | 1800mm x 1500mm Phenolic Board Partition with 1800mmx600mm Door w/ Accessories (2pc. Rising Hinge with indicator lock, Plastic door knob, adjustable foot (3pc), Coat Hook | 1 | unit | /uni | |
| | 5 | 2700mm x 3850mm Partition Wall, 1/4" Thick Tempered Glass (Clear), 1 3/4" x 4" Tubular Framing (Powder Coated White) | 300 | sq.ft. | /sq.fi | |
| | | | | IVIAIE | KIML COST | |

| o. [| | no. of units | EQUIPMENT | QUA | YTITY | UNIT COST | AMOUNT |
|------|---|--------------|-----------|-----|--------|-----------|--------|
| | 1 | 1 | | 1 | day | day/ | |
| _ | | | | | EQUIPM | ENT COST | |

| | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | AMOUNT |
|---|--------------------|-----------------|-----|---------|-----------|--------|
| 1 | 1 | Foreman | 5 | day | day/ | |
| 2 | 3 | Skilled Laborer | 5 | day | day/ | |
| | | | | LABO | R COST | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscellaneou | |
|-----------------------------------------------|---------------|
| | |
| contractors profit | |
| | TOTAL MARK-UP |





C. Value Added Tax, VAT (OCM + Contractor's Profit + Direct Cost)

5%

TOTAL INDIRECT COST

C. TOTAL COST

a. DIRECT COST + INDIRECT COST





IX. OTHER GENERAL

| / | Quantity: | 1 | lot |
|---|-----------|---|-----|

A. DIRECT COST

| a. | PARTICULARS | QUANTITY | | UNIT COST | AMOUNT |
|----|--------------------------------------------------|----------|---------|-----------|--------|
| | Cylinder Testing for Concrete Samples (3000 PSI) | 9 | pc. | /pc. | |
| _ | | | MATERIA | AL COST | |

| b. | no. of units | | EQUIPMENT | | YTITY | UNIT COST | AMOUNT |
|----|--------------|--------------|--------------------------|----|---------|-----------|--------|
| T | 1 | Personal Pro | otective Equipment (PPE) | 15 | рс | pc/ | |
| L | | | | | EQUIPME | NT COST | |

| | no. of manpower | LABOR | NO. | OF DAYS | UNIT COST | |
|---|--------------------|----------------|-----|---------|-----------|--|
| 1 | 1 | Safety Officer | 20 | day | day/ | |
| | | | | LABOR | RCOST | |

TOTAL DIRECT COST

B. INDIRECT COST

| a. OCM(Overhead, Contingencies, Miscellaneous) | 0% | | |
|-------------------------------------------------|----|---------------|--|
| b. CONTRACTORS PROFIT | 0% | | |
| | | TOTAL MARK-UP | |

| C. | Value Added Tax, VAT (OCM + Contractor's Profit + Direct Cost) | 5% | |
|----|----------------------------------------------------------------|----|--|

TOTAL INDIRECT COST

C. TOTAL COST

| a. DIRECT COST + INDIRECT COST | |
|--------------------------------|--|





| Λ | Quantity: | 1lot | | | | | |
|----------------|---------------------|------------------------------------------------|-----------------------------------------|-----------------|---------|--------|--------|
| A. | DIRECT COST | | | | | | |
| a. | PAR | TICULARS | QUA | NTITY | UNIT C | OST | AMOUNT |
| | 1 Tarpaulin 8'x8' (| With Frame) | 1 | pc. | | /pc. | |
| | | | | MATERIA | AL COST | | |
| b. | no. of units | EQUIPMENT | QUA | NTITY | UNIT C | OST | AMOUNT |
| | | | | EQUIPME | NT COST | | |
| | | | | | | | |
| c. | no. of manpower | LABOR | NO. 0 | F DAYS | UNIT C | OST | AMOUNT |
| c. | no. of manpower | LABOR | NO. 0 | F DAYS LABOR | | OST | AMOUNT |
| c. | no. of manpower | LABOR | | | COST | OST | AMOUNT |
| | no. of manpower | | | LABOR | COST | OST | AMOUNT |
| В. | INDIRECT COST | Γ | 1 | LABOR | COST | OST | AMOUNT |
| В. | INDIRECT COST | T ntingencies, Miscellaneous) | 1 | LABOR | COST | | AMOUNT |
| В. | INDIRECT COST | T ntingencies, Miscellaneous) | 1 | LABOR | COST | | AMOUNT |
| B. a. b. | INDIRECT COSTO | T ntingencies, Miscellaneous) | 000000000000000000000000000000000000000 | LABOR | COST | | AMOUNT |
| B. a. b. | INDIRECT COSTO | T ntingencies, Miscellaneous) FIT | 0000 | LABOR OTAL DIR | COST | ARK-UP | AMOUNT |



CONSTRUCTION SAFETY AND HEALTH PROGRAM

INTRODUCTION

The Construction Safety and Health Program outlines the mandatory policies, procedures, and standards necessary to ensure the safety, security, and well-being of all personnel engaged in the Construction of a one-storey Childminding center located at the area, south of the New Admin Building at Laoag International Airport.

This program is intended to identify, control, and mitigate occupational hazards, ensure strict regulatory compliance, and maintain the highest standards of occupational health and safety in accordance with all applicable aviation and construction industry regulations. The contractor shall be required to implement and strictly adhere to the provisions set forth herein to maintain a safe and hazard-free working environment while minimizing disruptions to airport operations.

TABLE OF CONTENTS

A. Safety Orientation and Seminar

To ensure compliance with occupational safety standards and aviation regulations, all contractor personnel shall be required to attend mandatory safety orientations and seminars. These programs are essential are essential for mitigating workplace hazards, ensuring compliance with aviation safety protocols, and fostering a secure and efficient working environment.

The required orientations and seminars shall include, but are not limited to, the following:

- a. Security Awareness Seminar
- b. Pre-Construction Meeting

B. Transport

The contractor shall provide the necessary service vehicles to facilitate effective communication and reliable transportation are essential for ensuring the smooth execution of the project and maintaining operational safety within the airport premises.

 Service Vehicles – The contractor shall make available, during the performance of the contract, at least (1) service vehicle with good





condition, for use by the airport authority's representative/engineers for the purpose of inspection, monitoring, measuring, laboratory testing and other activities relative to the implementation of the project.

C. Manpower Schedule

The Minimum manpower required during contract implementation shall be:

| No. of Manpower | Technical Personnel | Relevant Experience / Certificates Required |
|--------------------|---------------------|----------------------------------------------------------------|
| 1 | Safety Officer | 2years supervisory experience with safety training certificate |
| 1 | Foreman | - |
| 2 | Mason | - |
| 2 | Carpenter | _ |
| 2 . | Skilled Laborer | - |
| 2 | Painter | - |
| 2 | Tile Setter | - |
| 2 | Electrician | - |
| 4 | Common Laborer | - |

The contractor shall provide the necessary manpower to properly accomplish all necessary related works. The contractor shall designate a competent representative who shall be available at the area to oversee working operation being carried out and to receive instructions from the Airport officials. The contractor's authorized representative shall be responsible for the overall management and coordination of work to be performed as contract provisions and shall act as central point with the government agency. The contractor's authorized representative shall have full authority to act thereat in behalf of the contractor's name while in the premises.

1. Identification

The Contractor's personnel shall be recognizable while in airport premises. This will be accomplished by the used of uniforms and printed with the company's name of the contractor. All expenses for uniforms and badges shall be borne by the contractor. All contractor's personnel shall always be in uniform.





D. Work Schedule

The Contractor shall perform the Construction of Covered Parking at New Admin Building in compliance with the rules and policies of the airport.

The Contractor shall provide the necessary manpower, tools, equipment, materials and supplies to ensure timely accomplishment and delivery with the ultimate objective of delivering satisfactory on time result and performance.

1. Working Time

- Work is done regularly at daytime. Work operations is conducted within the period of 6:00 AM to 6:00 PM, with up to daily work duration of twelve (12) hours a day, six days a week including holiday. Also, the contractor/service provider shall have the option to submit a request to the CAAP-LIA Authorities for approval to conduct work during the nighttime hours, specifically between 10:00 PM and 6:00 AM, contingent upon the completion of all flight operations. Such request shall be subject to the CAAP-LIA Authorities' discretion and approval following review.
- Work operations shall be temporarily paused when deemed necessary, or when the operational area directly affects passenger flow and airport traffic during flight hours, ensuring minimal inconvenience while maintaining safety and efficiency.

E. Guidelines

The contractor shall always establish a complete quality control program to adhere with the following requirements while carrying out his function and responsibilities during the implementation of the contract.

1. Quality Assurance and Corresponding Penalties

The Contractor shall establish a system of quality control program to assure that the requirements of the contract are provided as specified. One copy of the contractor's quality control program shall be submitted to the Authority prior to start of the contracted services. An updated copy must be provided as changes occur. The program shall include but not limited to the following.





CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

- An inspection system, covering all the services to be performed under the contract. This must specify areas to be inspected on either a scheduled or unscheduled basis or such personnel who will perform the inspection.
- A method for identifying deficiencies in the quality of services rendered, before the level of performance becomes unacceptable.
- Contractor shall provide the following uniform to all its employees:
 - A shirt with a contractor's logo/name with pants of any color or any equivalent uniform acceptable to CAAP-LIA
 - A penalty amounting to Fifty Pesos (P 50.00) per day per person shall be imposed on personnel who are not in prescribed uniform while on duty.

2. Safety and Security Measures

The Contractor shall adhere to all standards and recommended practices stipulated by the airport authority and shall, under no circumstances, violate standard rules and regulations.

- The Contractor and his employees shall always comply with the security and safety requirements imposed by the management while in the airport premises.
- The Contractor is hereby instructed that aircraft operations and movements and the safety thereof, shall always take precedence over any operation.
 - In case of within the restricted area, a presence of authorized handheld radio operator is assigned and shall obtain clearance from the Control Tower from time to time for thorough safely.
- The Contractor shall, always keep paved surfaces such as runways, taxiways and hard stands free from hazardous materials.





TECHNICAL SPECIFICATION

I. INTRODUCTION

The Civil Aviation Authority of the Philippines, Area I, includes the Construction of a one-storey Childminding center located at the area, south of the New Admin Building at Laoag International Airport in its Annual Procurement Plan. This project aims to provide sheltered parking spaces that protect vehicles from various environmental elements and enhance overall convenience and safety at a portion of the New Vehicular Parking Area.

This project involves the construction of a One-Storey Childminding Center to provide safe, supervised care for children of employees. Therefore, the Authority is imposed to hire the services of a private contractor/supplier to undertake the construction of the project. The contractor/supplier shall comply with the provisions of this Term of Reference from the onset until the end of the implementation.

II. STATEMENT OF WORK

A. Work Breakdown Structure

CIVIL WORKS

a) Site Works

The work includes the supply of labor and equipment necessary to complete the demolition of a portion of the existing sidewalk, demolition of existing wheel stoppers and provision of new ones, to complete the excavation & disposal of soil for footings and other structural members as specified on the approved plans. Excavation and disposal must be in proper coordination with the Project-in-Charge to avoid disturbance to the existing structure of the area and other scope as indicated on the approved plans. The Contractor must provide equipment for hauling and disposal of excavated materials and site cleanup.

| | Quantity |
|--------------------|--------------|
| Area of Demolition | 1.5 cu.m. |
| Excavation Volume | 6.3 cu.m |
| Backfilling Works | 46.25 cu.m. |
| Gravel Bedding | 6.8025 cu.m. |





b) Concreting Works

The work includes all materials, labor, and tools/equipment needed to complete the concreting work of column pedestals and footings including the fabrication and installation of reinforcing bars and formworks as indicated on the approved plans. The strength of concrete will be 3000psi. Samples shall be collected and are due for Cylinder Testing to any DPWH-accredited Testing Center. Materials to be used and workmanship must be approved by the Project In-Charge assigned by CAAP.

Concrete Volume = 18.32 cu.m.

c) Masonry Works

The work includes all materials, labor, and tools/equipment needed to complete the masonry works including the fabrication and installation of reinforcing bars and plastering as indicated on the approved plans. Materials to be used and workmanship must be approved by the Project In-Charge assigned by CAAP.

Total Area of Masonry Works = 167 sq.m.

d) Roofing Works

The work includes all materials, labor, and tools/equipment needed to complete the installation of 0.60mm thk. Rib-Type Metal Roof Tile, C-purlins, aluminium insulation foam and other roofing accessories as indicated on the approved plans. Materials to be used and workmanship must be approved by the Project In-Charge assigned by CAAP.

Total Roofing Area = 65 sq.m.

e) Ceiling Works

The work includes the supply of labor, materials, tools and equipment needed to complete the ceiling works using PVC Ceiling Panel $8 \times 250 \times 2950$ mm, wall angle, blind rivets, PVC Accessories: H-type and U-type and 4.5mm thk. $\times 4' \times 8'$ fiber cement board on areas included in the approved plans. The installation of ceiling boards and other accessories must have the approval of the Project-in-Charge based on the approved plans prior to purchase and installation.

Total Area of Ceiling Works = 55 sqm





f) Painting Works

The work includes all materials, labor, and equipment/tools to complete the painting works of the exterior wall and interior wall, using, Water proofing, masonry putty, Semi-gloss Latex Paint as indicated on the approved plans. Materials to be used and workmanship must be approved by the Project In-Charge.

Total Area of Painting Works = 183.50 sqm

g) Tile Works

The work includes the supply of labor, materials, tools and equipment needed to complete the installation of tiles using 30cm x 30cm Matte Rustic Tiles, Material: Ceramic, Color: White Sugar Finish; 30cm x 60cm Matte Finish, Material: Ceramic, Color: Viene Ash; 60cm x 120cm Matte Rustic Tiles, Material: Porcelain, Color: Vernia White, Edge: Rectified; 30cm x 30cm Matte Rustic Tiles, Material: Ceramic, Color: Taupe (Gray) on areas included in the approved plans. The installation of tiles and other accessories must have the approval of the Project in-Charge based on the approved plans prior to purchase and installation.

Total Area of Tile Works = 102.05 sqm

h) Cladding Works

The work includes the supply of labor, materials, tools and equipment needed to complete cladding works using 4' x 8' x 3mm Al. thickness Aluminum Composite Panel; 202mmx30mmx2.85m WPC Indoor Panel and 224x26x2900mm WPC Outdoor Cladding on areas included in the approved plans. The installation of tiles and other accessories must have the approval of the Project in-Charge based on the approved plans prior to purchase and installation.

PLUMBING WORKS 11.

The work includes materials, labor, equipment/tools and testing for the installation of waterline, sanitary line, septic tank, and plumbing fixtures including standard accessories using PVC Vanity Wall Hung Cabinet, One Piece Skirted Water Closet, 350x380x750mm Urinal with Sensor, 2000L Pp/Pe Septic Tank, PPR Pipes and uPVC Pipes as indicated on the approved plans.



III. ELECTRICAL WORKS

The work includes materials, labor, and equipment/tools for the installation of lighting and power conduits including panel board, conduit fittings, pullwire, utility boxes, junction boxes, pull boxes, other hardware and accessories, lighting and ventilation fixtures: 300mmx1200mm Recessed Panel Light 48w; Pin Lights LED Bulb Concealed 6"x12Watts; 12-Inch Wall Mounted Exhaust Fan, to complete the system. Routing of conduits shall be for approval of the CAAP Project In Charge. All conduits and fittings shall be Underwriters Laboratories (UL) Listed.

IV. DOORS AND PARTITIONS

The work includes all materials, labor and tools for installation of doors and windows complete with hardware and accessories including jamb and header using 2100mm x 1800 mm, 1/2" Tempered Glass Double Swing Door (Frameless, Complete with door closer, stainless steel door handle - H-Type); 2100mm x 900 mm, 1/2" Tempered Glass Swing Door; 2100mm x 800mm Single Leaf PVC Moulded Door (Complete with 4pc. Ball Bearing hinge, Lever type (zinc alloy) Single cylinder deadbolt, Plain Matte Finish Gray); 1800mm x 1500mm Phenolic Board Partition with 1800mmx600mm Door w/ Accessories (2pc. Rising Hinge with indicator lock, Plastic door knob, adjustable foot (3pc), Coat Hook and 2700mm x 3850mm Partition Wall, 1/4" Thick Tempered Glass (Clear), 1 3/4" x 4" Tubular Framing (Powder Coated White) as indicated on the approved plans. Materials to be used and workmanship must be approved by the Project In-Charge assigned by CAAP.

B. Equipment, Tools and Consumables required to be used for the project:

- a) 1 unit Concrete Cutter
- b) 1 unit Jackhammer
- c) 1 unit Plate Compactor
- d) 1 unit One Bagger Mixer
- e) 1 unit Concrete Vibrator
- f) 1 unit Welding Machine
- g) 1 unit Hand Router
- h) Scaffolding

The Contractor shall provide the required number of equipment, tools and consumables to accomplish all necessary works provided in the contract. The contractor's equipment provided therein shall be used exclusively for the contracted services.

The use of other kind of equipment other than that stated thereof will not be permitted, unless otherwise approved by the authority. Any delay caused, by





stoppage of work being authorized by the office concerned will not be taken against the contractor.

C. Period of Implementation

The contract shall be implemented for a total of 100 Calendar days, inclusive of Sundays, Holidays and 21 unworkable days for the Laoag International Airport FY2025. Provided that the contractor will only proceed upon written notice from the duly authorized representative of the Authority to commence with the project, which notice must not be less than seven (7) days from the start date.


D. Progress Billing

The contractor/service provider may submit a Statement of Work Accomplishment (SWA) or progress billing after completing each 20% milestone of the project, provided that such submission shall be made no more than once (1) per calendar month. The submitted SWA or progress billing shall be accompanied by geotagged (date and location) progress photos, properly labelled as 'Before,' 'During,' and 'After.' The End-User or Project-in-Charge shall review and reconcile the contractor's SWA with the verified actual accomplishments. Based on this reconciliation, the End-User or Project-in-Charge shall certify the amount to be paid to the contractor as progress payment.





PERSPECTIVE



SITE DEVELOPMENT PLAN



VICINITY MAP



PREPARED

RENZ ALDRINE A. CORPUZ

CHECKED/VERIFIED:

JOEFFREY B. LAGADON Engineer II, FIC -BGM PROJECT TITLE:

CONSTRUCTION OF CHILDMINDING CENTER


LOCATION:


BRGY. 36 ARANIW, LAOAG CITY

RONALD V-ESTABILLO
CIVIL AVIATION AREA MANAGER, AREA 1

SCALE:

Front Page A-1





Concrete Pavement

REPUBLIC OF THE PHILIPPINES

Finish Floor Line 1:100

RENZ ALDRINEA. CORPUZ CHECKED/VERIFIED: JOEFFREY B. LAGADON Engineer II, FIG -BGM CIVIL AVIATION AUTHORITY OF THE PHILIPPINES


PROJECT TITLE: CONSTRUCTION OF CHILDMINDING CENTER LOCATION:


BRGY. 36 ARANIW, LAOAG CITY


RONALDV. ESTABILLO CIVIL AVIATION AREA MANAGER, AREA 1


SCALE: 1:100

Floor Plan A-2










DOORS AND WINDOWS SCHEDULE





PREPARED:

RENZ ALDRINE A. CORPUZ

Engineer

CHECKED/VERIFIED:

JOEFFREY B. LAGADON

Engineek II, FIC. BGM

PROJECT TITLE:
CONSTRUCTION OF CHILDMINDING CENTER


LOCATION:

BRGY. 36 ARANIW, LAOAG CITY

RONALD WESTABILLO
CIVIL AVIATION AREA MANAGER, AREA 1

SCALE: 1:50

Doors and Windows A-6



Ceiling Plan 1:100

CONSTRUCTION OF CHILDMINDING CENTER

LOCATION:

BRGY. 36 ARANIW, LAOAG CITY

Floor/Floor Finishes


Reflected Ceiling IA-71


SCALE: 1:100

REPUBLIC OF THE PHILIPPINES CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

PREPARED: RENZ ALDRINE A. CORPUZ CHECKED/VERIFIED: JOEFFREY B. LAGADON Engineer II, FIC-BGM

1:100





REPUBLIC OF THE PHILIPPINES
CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

PREPARED:

RENZ ALDRINE A: CORPUZ

Ergineer

CHECKED/VERIFIED:

JOEFFREY B. LAGADON

Engineer II, FIG. BGM

PROJECT TITLE:
CONSTRUCTION OF CHILDMINDING CENTER

LOCATION:

BRGY. 36 ARANIW, LAOAG CITY

APPROVED: RONALD VESTABILL

SCALE: 1:100

Foundation Plan S-1

CONSTRUCTION NOTES: CONSTRUCTION NOTES AND TYPICAL DETAILS APPLY TO ALL UNLESS OTHERWISE SHOWN OR NOTED. MODIFY TYPICAL DETAILS AS DIRECTED TO MEET SPECIAL CONDITIONS. SHOP DRAWNINGS WITH ERECTION AND PLACING DIAGRAMS OF ALL STRUCTURAL STELL, MISCELLANEOUS IRON, PRE-CAST CONCRETE ETC. SHALL BE SUBMITTED FOR ENGINEER'S APPROVAL BEFORE FABRICATION. 3. CONTRACTOR SHALL VERIFY ALL DIMENSIONS BEFORE ALL WORK IS TO BEGIN. CHECK WITH MECHANICAL AND ELECTRICAL CONTRACTORS FOR CONDUITS, PIPE SLEEVES, ETC. TO BE EMBEDED IN CONCRETE.

4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE ADEQUATE SHORNOS AND BRACING OF THE STRUCTURE FOR ALL LOADS THAT MAYBE IMPOSED DURING CONSTRUCTION. B: CONCRETE AND REINFORCEMENT

- I. ALL MATERIALS WORKMANSHIP SHALL CONFORM WITH THE LATEST BUILDING CODE OF AMERICAN CONCRETE INSTITUTE (ACI-318).
- 2. ALL CONCRETE SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH AT THE END OF TWENTY EIGHT (28) DAYS WITH CORRESPONDING MAXIMUM SIZE AGGREGATE AND SLUMPS AS FOLLOWS

28 DAYS STRENGTH MAX. SIZE AGGREGATE MAX. SLUMP SLAB ON GRADE WALL FOOTING SUSPENDED SLAB COUNTER TOP 1 In. (25 mm) 4 in. (100 mm) 3000 PSI FOUNDATION & COLUMN, BEAM 3/4 in. (19 mm) 4 in. (100 mm)

ALL OTHERS 4000 PSI 3/4 ln. (19 mm) 5 in. (125 mm)

- 3. REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 40 FOR \$12 & SMALLER REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60 FOR \$16 & BIGGER 4. IN GENERAL, THE LATEST EDITION OF ACI—315, MANUAL OF STANDARD PRACTICE DETAILING REINFORCED CONCRETE STRUCTURES SHALL BE ADHERED TO UNLESS OTHERWISE SHOWN OR NOTED.
- 5. MAINTAIN MINIMUM CONCRETE COVER FOR REINFORCING STEEL AS FOLLOWS.

 SUSPENDED SLABS 3/4 in. (19mm)

 SLAB ON GRADE 1 1/2 in. (38mm)

 WALLS ABOVE GRADE 1 in. (25mm)
 - BEAM STIRRUPS AND COLUMN TIES 1 1/2 in. (38mm) WHERE CONCRETE IS EXPOSED TO EARTH BUT POURED AGAINST FORMS 2 in. (50mm) WHERE CONCRETE IS DEPOSITED DIRECTLY AGAINST EARTH 3 In (75mm)
- SEPLICES SHALL BE SECURELY WIRED AND SHALL LAP OR EXTEND IN ACCORDANCE WITH TABLE 1 (TABLE OF LAP SPLICE AND ANCHORAGE LENGTH) UNLESS OTHERWISE SHOWN ON DRAWINGS, SPLICES SHALL BE STAGGERED WHENEVER POSSIBLE.
- ALL ANCHOR BOLTS, DOWELS, AND OTHER INSERTS, SHALL BE PROPERLY POSITIONED AND SECURED IN PLACE PRIOR TO PLACING OF CONCRETE. 8. CONTRACTOR SHALL NOTE AND PROVIDE ALL MISCELLANEOUS CURBS, SILLS, TOOLS, EQUIPMENTS AND MECHANICAL BASES THAT ARE REQUIRED BY THE ARCHITECTURAL, ELECTRICAL, AND MECHANICAL DRAWINGS.
- ALL CONCRETE SHALL BE KEPT MOIST FOR A MINIMUM OF SEVEN (7) CONSECUTIVE DAYS IMMEDIATELY AFTER POURING BY THE USE OF WET BURLAP, FOG SPRAYING, CUBING COMPOUNDS OR OTHER APPROVED METHODS.
- 10. STRIPPING OF FORMS AND SHORES
 REFER TO TECHNICAL SPECIFICATIONS

C: CAMBER REQUIREMENTS

- UNLESS PTHERWISE NOTED ON THE PLANS OR SPECFICATIONS, CAMBER ALL R.C BEAMS AT LEAST 10mm FOR EVERY 4000mm OF CLEAR SPAN EXCEPT CANTILEVERS WHICH SHALL BE 50mm FOR EVERY 3000mm OF CLEAR SPAN.
- UNLESS OTHERWISE NOTED IN PLANS OR SPECIFICATIONS, CAMBERS ALL SLABS 8mm 3000mm OF SHORTER SPAN AND 14mm. FOR EVERY 2000mm OF SLABS CANTILEVER SPAN.

D: MASONRY AND CONCRETE BLOCKS


- ALL-LOAD BEARING TYPE CONCRETE BLOCKS SHALL HAVE A UNIT WEIGHT NOT TO EXCEED 80 PCF. FOR LOAD BEARING TYPE CONCRETE BLOCKS A MINIMUM COMPRESSIVE STRENGTH OF 6.90 MPA. SHALL BE DEVELOPED.
- PROVIDE 1-016 VERTICAL BARS AT CORNERS, INTERSECTIONS, END OF WALLS, EACH SIDE OF OPENINGS.
- 3. LINTEL BEAMS SHALL BEAR AT LEAST 8 INCHES (200 MM.) ON EACH SIDE OF MASONRY WALL OPENING.
- 4. WALL REINFORCEMENTS SHALL BE AS FOLLOWS:
 - WALL THICKNESS VERTICAL REINFORCEMENT HORIZONTAL REINFORCEMENT ø10 @ 600 mm ø10 @ 600 mm ø10 @ 600 mm
- REINFORCING BARS SHALL BE LAPPED A MINIMUM OF 40 BARS DIAMETERS WHERE SPLICED DOWELS FROM CONCRETE FOOTINGS OR SLABS EXTEND INTO THE BLOCK WALL A MINIMUM OF 40 BAR DIAMETERS, AND DOWELS TO MATCH VERTICAL REINFORCEMENTS OF WALL.
- ALL CELLS CONTAINING REINFORCING BARS OR INSERTS SHALL BE SOLIDLY FILLED WITH CONCRETE GROUT, (REFER TO SPECIFICATIONS).

- ALL STRUCTURAL STEEL SHAPES SHALL CONFORM TO STD. REQUIREMENTS OF AISC FOR ASTM A36 STEEL
- ALL COLD FORMED STEEL SHAPES SHALL CONFORM TO STD. REQUIREMENTS OF AISI FOR JIS G3141 SPCC
- 3. ALL WELDS SHALL CONFORM WITH AWS STD.
 4. CONNECTORS
 BOLTS ASTM A307 OR ASTM A325 AS SPECIFIED
 WELDS EBOXX ELECTRODE

F: FOUNDATION

- FOUNDATION IS DESIGNED BASED ON THE ASSUMPTION OF 120 KPA SOIL BEARING CAPACITY FOR FOOTING NOT LESS THAN 1.5M.
- 2. FOUNDATION SHALL REST ON NATURAL SOIL, UNLESS OTHERWISE NOTED BY THE ENGINEER, NO PART OF THE FOUNDATION SHALL REST ON FILL.

 3. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AFTER FOOTING EXCAVATION HAVE BEEN COMPLETED AND PRIOR TO CONCRETING TO CONFIRM THE DESIGN SOIL BEARING CAPACITY.
- THE CONTRACTOR SHALL HAVE THE SOLE RESPONSIBILITY TO DEWISE & IMPLEMENT EXCAVATION PROCEDURES THAT WILL ENSURE SAFETY OF LIFE & PROPERTY.




NOTES:


PARAMETERS 1. YIELD STRESS OF HOOPS-40 KSI MATERIAL psi MPo ACI 318-05
f'c 4,000 27.6 DEV'T. & SPLICE LENGTH


TIE Ø 10 STIRRUP Ø


- D = USE MAXIMUM COLUMN DIMENSION 1/6 CLEAR HEIGHT OR 18" (450mm) WHICHEVER IS GREATER. fy 60,000 414 Ø16 & HIGHER NUMBER OF HOOP TIES SAME AS PER COLUMN TIES SCHEDULE. fyh 40,000 276 ø12 & LOWER
 - ALL CONCRETE REINFORCEMENT DETAIL SHOULD BE DONE INACCORDANCE WITH

| BAR Ø | ANCHORAGE | Ldh | STANDA | ARD H | | BEAM COMP. | | | N LAP SPL | JCE (mr |) | UNIT WI |
|-------|------------|------|--------|-------|----------|-------------|-------|-------------|-------------------|---------|--------|---------|
| (mm) | LENGTH(mm) | (mm) | 90" | 180 | 135'-90' | SPLICE (mm) | CLASS | TOP BUR | EAU BOITON BAS | 16.0 | SPIRAL | (kg/m) |
| 10 | 600 | 150 | 160 | 110 | 120~120 | | Â | 310 | 300 | 300 | 300 | 0.616 |
| 12 | 600 | 150 | 200 | 120 | 130~130 | 300 | A | 410 540 | 310 | 310 | 310 | 0.888 |
| 16 | 780 | 310 | 260 | 130 | 160~160 | 470 | Â | 1010 | 800 | 610 | 610 | 1.578 |
| 20 | 970 | 390 | 320 | 160 | 200~320 | 580 | A | 990 1290 | 760 990 | 760 | 760 | 2.466 |
| 25 | 1,210 | 480 | 400 | 200 | 250~400 | 730 | A | 1550 | 1190 | 1190 | 1190 | 3.853 |
| 28 | 1,370 | 540 | 480 | 260 | | 820 | À | 1735 | 1330 | 1330 | 1330 | 4.834 |









DOWEL BARS TO MATCH VERT, BARS

REINFORCING BAR FOR SLAB OPENING

1-16¢ CONT. HOR. BARS FOR FLOOR SLAB ONLY

VERTICAL & HORIZONTAL

OPENING SIZE


TYPICAL DETAIL OF LINTEL BEAM

Reinforcement

Longitudinal Bottom Bar

UNDER 600

UNDER 800



0.4m

400x250MM CONCRETE


COLUMN WITH 4-Ø16MM

MAIN REINFORCEMENT

BARS AND Ø10MM DRSB LATERAL TIES SPACED @

150MM

SECTION VIEW



F1/C1 DETAILS

SCALE

THE HERE AND THE HEATT

F1/C2 DETAILS

0.25m

250x250MM CONCRETE

COLUMN WITH 4-Ø16MM

MAIN REINFORCEMENT

BARS AND AIDMA OKSB

| Size | (mm) | Top P | einforce | ment | Bottom | Reinford | ement | |
|------|------|-----------------------|----------|-----------------------|--------|-----------------------|--------|-------------------------------------------------------------------------------------|
| b | d | Left | Mid | Right | Left | Mid | Right | Stirrup |
| 250 | 400 | 2-16mm + 2-16mm | 2-16mm | 2-16mm + 2-16mm | 2-16mm | 2-16mm + 1-16mm | 2-16mm | 10mm dia. RSB Stirrups Spaced @ 1-50mm, 2-75mm, 3-100mm, 3-150mm rest @ 200mm |

Bottom Reinforcement

Transverse Bottom Bar

FIN. FLR. LVL.

AT CHB WALL OPENING

APPROVED:

| COLUMN | Dimens | ion (mm) | | Reinforcement | |
|--------|--------|----------|------|------------------------|--|
| MARK | D B | | (mm) | Countinous Vertical Ba | |
| C1 | 400 | 250 | 50 | 4-16mm RSB | |
| C2 | 250 | 250 | 50 | 4-12mm RSB | |



CHECKED/ VERIFIED BY:

PROJECT TITLE:

ALL JOINTS AND CEILS

CONSTRUCTION NOTES.

SHALL BE FILLED WITH CONCRE

SEE CONSTRUCTION HOTES FOR MASONRY WALL REIN-FORCEMENTS(TYPICAL)

FIN. FLR. LVL

Dimension (mm)

1000

250

1000

MARK

BEAM

RB-1

RB-2

DESIGNATION

CONSTRUCTION OF CHILDMINDING CENTER

PROJECT LOCATION:


BRGY. 36 ARANIW, LAOAG CITY


RONALD V. ESTABILLO CIVIL AVIATION AREA MANAGER, AREA I DRAWING SCALE: AS SHOWN


SHEET NO .:


CIVIL AVIATION AUTHORITY OF THE PHILIPPINES

JOEFFREY B. LAGADON










2 Section 2

3 Section 9

Section 10





Republic of the Phillipines

CIVIL AVIATION AUTHORITY OF THE PHILLIPINES

ROMUALDO U. BAYANGOS

ELECTRICALENGI NEER

JOEFFREY LUAGADON

ENGINEER II - FIC/BGN

PROJECT TITLE:

Construction of Childminding Center

OCATION/ADDRESS:

Laoag International Airport, Brgy. 36 Araniw, Laoag City RONALD V. ESTABILLO

CIVIL AVIATION AREA MANAGER, AREA 1 HEAD, CLUSTER AREA CENTER 1 WATER AND SANITARY LAYOUT

PL01

1:100